HIGAIN LINE UNIT

Model	List Number	Part Number	CLEI Code
HLU-319	5E	150-1140-55	T1L2B40A



PAIRGAIN TECHNOLOGIES, INC.
ENGINEERING SERVICES TECHNICAL PRACTICE
SECTION 150-319-155-04

REVISION HISTORY OF THIS PRACTICE

Revision	Release Date	Revisions Made
01	May 6, 1998	Initial release
02	June 1, 1998	Modified alarm diagnostics, miscellaneous edits
03	April 19, 1999	Revised diagnostic tables
04	September 20, 1999	Troubleshooting screens added

© Copyright 1999 PairGain Technologies, Inc.

PairGain and HiGain are registered trademarks of PairGain Technologies, Inc. All other product names mentioned in this practice are used for identification purposes only and may be trademarks or registered trademarks of their respective companies.

Information contained in this document is company private to PairGain Technologies, Inc., and shall not be modified, used, copied, reproduced or disclosed in whole or in part without the written consent of PairGain.

Information furnished by PairGain Technologies is believed to be accurate and reliable. However, no responsibility is assumed by PairGain Technologies for its use; nor for any infringement of patents or other rights of third parties which may result from its use. No license is granted by implication or otherwise under any patent or patent rights of PairGain Technologies. PairGain Technologies reserves the right to change specifications at any time without notice.

USING THIS TECHNICAL PRACTICE

The following conventions are used in this manual:

- Monospace type indicates screen text, including text you type at a screen prompt.
- Keys you press are indicated by small icons such as **ENTER**. Key combinations to be pressed simultaneously are indicated with a plus sign as follows: **CTRL** + **ESC**.
- Three types of messages, identified by icons, appear in text.



Notes contain information about special circumstances.



Cautions indicate the possibility of equipment damage or personal injury.



The Electrostatic Discharge (ESD) Susceptibility symbol indicates that a device or assembly is susceptible to damage from electrostatic discharge.

For a list of abbreviations used in this document, refer to "Appendix E - Glossary" on page 68.

DOCUMENTATION

If you have comments on this PairGain document, send an email to *technical_publications@pairgain.com*. Type the product name and the section number of the document in the subject area of the email message.

INSPECTING THE SHIPMENT

Upon receipt of the equipment:

- Unpack each container and inspect the contents for signs of damage. If the equipment has been damaged in transit, immediately report the extent of damage to the transportation company and to PairGain. Order replacement equipment, if necessary.
- Check the packing list to ensure complete and accurate shipment of each listed item. If the shipment is short or irregular, contact PairGain as described in the Warranty located inside the back cover. If you must store the equipment for a prolonged period, store the equipment in its original container.

TABLE OF CONTENTS

Overview		_ 1
Features		1
	Product Enhancements	1
	Standard Features	2
Compati	bility	2
Applicat	ions	2
	HiGain Doubler Applications	3
	Personal Communications System Applications	3
Front Panel		_4
Installation		_ 8
Verifica	tion	9
	Verification without a Downstream Device	9
	Verification with a Downstream Device	9
Provisio	ning Requirements	10
Provisioning		11
Using th	e MODE and SEL Buttons	11
	Setting Options through MODE and SEL	11
	Resetting to Factory Default Values	12
	Displaying System Parameter Settings	12
	Disabling an Alarm	12
	Loopback Modes	12
Using a	Maintenance Terminal	13
	Connecting to a Maintenance Terminal	13
	Accessing the Maintenance Terminal Screens	13
Using th	e Maintenance Terminal Screens	15
	View Span Status Screen	15
	Set Clock Screen	19
	System Settings Screen	20
	Loopback Mode Screen	26
	View Performance Data Screen	29
	View Performance History Screen	31
	View Alarm History Screen	34
	View System Inventory Screen	36
	View Troubleshooting Screen	38

Troubleshooting	42
System Alarms	42
Alarm Option for DLC Feed	43
Retiring System Alarms	43
Self Test	43
Loopback Operation	44
Generic Loopback Commands	44
Special Loopback Commands	46
Initiating a Manual Loopback Session	47
Loopback Test Procedures	48
General Troubleshooting Tips	48
GNLB Test Procedures	48
A1LB, A2LB, and A5LB Test Procedures	50
A3LB and A4LB Test Procedures	53
Appendix A - Specifications	54
HDSL Insertion Loss Guidelines	55
Power Consumption	55
Power Consumption without Doublers	55
Power Consumption with Doublers	56
Maximum Power Dissipation	58
Maximum Current Drain	58
HLU-319 List 5E Card Connector	59
Network Management Control Bus	59
Fuse Alarm	60
System Alarm Relay Output	60
Craft Port	61
Appendix B - Functional Operation	62
Timing	62
Ground Fault Detect	63
Appendix C - Compatibility	64
T1 Repeater Shelves and Related Equipment	64
HiGain Doubler Circuit Deployment	64

Table of Contents 150-319-155-04, Revision 04

Appendix D - Product Support	66
Technical Support	
World Wide Web	
Returns	
Appendix E - Glossary	68
Certification and Warranty	Inside Back Cover

150-319-155-04, Revision 04 List of Figures

LIST OF FIGURES

1. HLU-319 List 5E Front Panel	4
2. Installing the HLU-319 into a Shelf	8
3. Maintenance Terminal Main Menu	14
4. System Spans	15
5. Span Status Screen: No Doubler	16
6. Span Status Screen: Four Doublers (Span 5)	16
7. Set Clock Screen	19
8. System Settings Screen	20
9. Loopback Menu: No Doubler	27
10. Loopback Menu: Four Doublers	28
11. NLOC Loopback Mode Reported in the Maintenance Terminal Main Menu	29
12. Performance Data Screen: No Doubler	30
13. Performance Data Screen: Four Doublers (Span 5)	31
14. 31-Day Performance History Screen: No Doubler	32
15. 31-Day Performance History Screen: Four Doublers (Span 5)	33
16. Alarm History Screen: No Doubler	35
17. Alarm History Screen: Four Doublers (Span 5)	35
18. System Inventory Screen: No Doubler	37
19. System Inventory Screen: Four Doublers	37
20. Troubleshooting Screen for a Doubler Application	38
21. Troubleshooting Screen Describing Circuit Problem	38
22. Troubleshooting with Help	39
23. Troubleshooting with Margin Values	40
24. Troubleshooting with Insertion Loss Values	40
25. Troubleshooting with 24-Hour Errored Seconds (ES)	41
26. Troubleshooting with 24-Hour Unavailable Seconds (UAS)	41
27. Loopback Summary	44
28. Loopback Configurations	49
29. HLU-319 List 5E Card-edge Connector	59
30. RS-232 Craft Port Pinouts	61
31. HLU-319 List 5E Block Diagram	62

List of Tables 150-319-155-04, Revision 04

LIST OF TABLES

1.	Front-panel Description	5
2.	Front-panel Display Messages	6
3.	Navigational Keys on the Maintenance Terminal	13
4.	Maintenance Terminal Screens	14
5.	Span Status Fields and Descriptions	17
6.	HDSL System Alarms	18
7.	Loopback Messages	18
8.	HLU-319 List 5E System Settings Options	21
9.	Loopback Field Messages and Descriptions	27
10.	Errored and Unavailable Seconds Definitions	30
11.	Alarm History Fields and Descriptions	34
12.	HDSL System Alarms	42
13.	Summary of HiGain Loopback Codes	45
14.	Addressable Repeater Loopback Commands (A1LB, A2LB, A5LB)	50
15.	Addressable Repeater Loopback Commands (A3LB and A4LB)	53
16.	HDSL Loss Over Cables	55
17.	HLU-319 Power Parameters—No Doubler	55
18.	HLU-319 Power Parameters—Single Doubler (HDU-451 List 1 or 2)	56
19.	HLU-319 Power Parameters—Single Doubler (HDU-439 or HDU-437 Lists 1 and 1B)	56
20.	HLU-319 Power Parameters—Single Doubler (HDU-409 List 2, HDU-407 List 2, and HDU-404 List 2)	56
21.	HLU-319 Power Parameters—Two Doublers (HDU-451 List 3, 4, 3B or 4B)	57
22.	HLU-319 Power Parameters—Two Doublers (HDU-439 or HDU-437 List 1 and 1B)	57
23.	HLU-319 Power Parameters—Two Doublers (HDU-409 List 2, HDU-407 List 2, and HDU-404 List 2)	57
24.	HLU-319 Power Parameters—Three and Four Doublers (HDU-409 List 2, HDU-407 List 2, and HDU-404 List 2)	57
25.	HiGain Doubler Deployment Matrix	65

150-319-155-04, Revision 04 Overview

OVERVIEW

The PairGain® Line Unit HLU-319 List 5E is the Central Office (CO) side of a repeaterless T1 transmission system. When used in conjunction with a HiGain Remote Unit (HRU), the system provides 1.544 Mbps transmission on two unconditioned copper pairs over the full Carrier Service Area (CSA) range. The CSA includes loops up to 12,000 feet of 24 AWG or 9,000 feet of 26 AWG wire, including bridged taps. This line unit can be used with HiGain Doubler Units (HDUs) to extend reach.

FEATURES

Product Enhancements

- Five-span range with four doublers (60 kft, 24 AWG)
- Four line-powered spans (three doublers and one remote)
- Reduced power consumption
- Customer Disconnect Indicator (CDI) option
- Ultra-low wander (Stratum 1 compliant)
- Low line-power option (-140 Vdc) for circuits with a single doubler
- Selectable Power Feed (PWRF) modes: Auto, High and Low and Disabled
- Grounded loop detection on High-bit-rate Digital Subscriber Line (HDSL)
- Bipolar Violation Transparency (BPVT) options
- Bit Error Rate (BER) alarm options
- HRU loopback screen
- Inventory and troubleshooting screens
- Loss of Signal/Alarm Indicator Signal (LOS/AIS) payload alarm option
- Remote Loss of Signal (RLOS) disable alarm option
- Digital Data Service (DDS) latching loopback option
- Supports HRU-411 in Personal Communications System (PCS) applications
- Default setting screen option
- Payload (PL) or HiGain (HG) loopback source identification
- Remote Provisioning

Overview 150-319-155-04, Revision 04

Standard Features

- Selectable DS1 pre-equalizer
- Front-panel features:
 - Four-character status display
 - DS1 splitting and bridging access
 - Status LED
 - RS-232 craft port for connection to a maintenance terminal (ASCII terminal or a PC running a terminal emulation program)
- Compatible with Span Terminating Shelf (STS) high density shelves, and equivalent
- Selectable loopback activation codes
- Network Management and Administration (NMA) interface
- Lightning and power cross protection on HDSL interfaces
- Full duplex 2-Binary 1-Quartenary (2B1Q) HDSL transmission on two pairs at 784 kbps
- Margin threshold alarm

COMPATIBILITY

The HLU-319 List 5E is designed to be mounted in 3192 mechanics shelves. For a list of compatible shelves, see "Appendix C - Compatibility" on page 64.

All generations of HiGain HLU and HRU modules are compatible with each other. To take advantage of the enhanced features of newer HiGain doublers, refer to "HiGain Doubler Circuit Deployment" on page 64.

APPLICATIONS

HiGain systems provide a cost-effective, easy-to-deploy method for delivering T1 High Capacity Digital Service (HCDS) over metallic pairs.

- The service is deployed over two unconditioned, non-loaded copper pairs, yet it demonstrates a quality that is competitive with fiber optics.
- Conventional, in-line, T1 repeaters are not required.
- Cable pair conditioning, pair separation and bridged tap removal are not required.

In general, HiGain systems:

- Operate with any number of other T1, Plain Old Telephone Service (POTS), Digital Data Service (DDS) or other HiGain systems sharing the same cable binder group.
- Can be used with customers requiring DS1 service on a temporary or permanent basis.
- Provide a means of quickly deploying service in advance of fiber-optic transmission systems.

With a HiGain system, service can be provided within hours. Fiber-optic systems can be installed incrementally and cut-over from the installed HiGain system when convenient to do so.

150-319-155-04, Revision 04 Overview

HiGain Doubler Applications

For applications without doublers, the HLU-319 is directly connected to the HRU by the two HDSL cable pairs. The HLU-319 List 5E is compatible with all HiGain HRUs.

For doubler applications, one to four doublers may be used in the HDSL loops between the HLU and HRU.

- If the HRU is line-powered, the HLU-319 List 5E can power three doublers and the remote unit (HRU-402 or HRU-411) for a total of four spans.
- If the HRU is locally powered, the HLU can power up to four doublers for a total of five spans.



These extended ranges are only available when using the HDU-409, HDU-404 or HDU-407 micro-doublers with the HRU-411 or HRU-402. Older doublers (HDU-451, HDU-439 and HDU-437) cannot be used in circuits with more than two doublers in any line or local power system. For compatibility guidelines on mixing newer doublers with older HRU and HLU models, refer to "HiGain Doubler Circuit Deployment" on page 64.

For additional information about associated HiGain equipment, refer to the respective HiGain technical practice (see "Appendix D - Product Support" on page 66).

Personal Communications System Applications

The HLU-319 List 5E is required for PCS applications that use the HRU-411. The HRU-411 has an onboard 130 Vdc, 8.5 W power supply that can power the 200 mW PCS remote radio ports. The line unit recognizes the HRU-411 (if CPE POWER switch is set to ON) and performs the following two functions required by the HRU-411 to bring up the National Electric Code (NEC) radio port:

- Increases the HDSL line voltage to its high ±112 Vdc level with the PWRF option set to AUTO
- Enables HRU-411 to turn on its 130 Vdc radio port supply

Front Panel 150-319-155-04, Revision 04

FRONT PANEL

The HLU-319 List 5E front panel is shown in Figure 1. The front-panel components are described in Table 1 on page 5. For pinout diagrams of the HLU card-edge connector and the craft port, refer to "Appendix A - Specifications" on page 54.




Figure 1. HLU-319 List 5E Front Panel

150-319-155-04, Revision 04 Front Panel

 Table 1.
 Front-panel Description

Front-panel Feature	Function
List number	Identifies the version of the HLU-319.
Front-panel display	Displays four-character status, provisioning, and alarm system messages. The front-panel display illuminates when power is initially applied. To conserve power the display only remains on for 4 minutes. Using the MODE or SEL buttons reactivates the display and restarts the 4-minute timer. Refer to Table 2 on page 6 for a listing of the four-character messages.
Configuration number	Contains either a five or six-digit warranty configuration number or a stand-alone two or three-digit configuration number as follows:
	Digit 1 - Last digit of shipment year
	Digits 2 and 3 - Shipment month
	Digits 4, 5, and 6 - Configuration number
	The configuration number can also be found on a small bar label that contains the Julian date code and part number. This gummed label may be affixed to the PC board or to the front panel.
System option buttons (MODE and SEL)	Permits the user options to be monitored and modified without the need of a maintenance terminal. Used to initiate all HiGain loopbacks and to display DSX-1 line parameters and line unit identity.
Status LED	The status LED can report the following conditions:
Green	Normal operation
Flashing green	HDSL acquisition
Red	Fuse Alarm
Flashing red	System alarm
Yellow	Self Test is in process or an HLU-319 List 5E Customer Remote Loopback (CREM) or a Network Local Loopback (NLOC) is in effect.
Flashing yellow	HLU-319 List 5E is Armed to respond to Intelligent Repeater Loop (ILR) codes.
DSX-1 access jacks (DS1 Cross-connect frame)	XMT is the Transmit jack and RCV is the Receive jack for spanning and bridging.
Line	Provides splitting jack access to (XMT) and from (RCV), the HDSL span at the DSX-1 interface. Breaks the XMT and RCV paths to permit test signal insertion and retrieval.
BRG	Provides non-intrusive bridging jack access to (XMT) and from (RCV) the HDSL span at the DSX-1 interface. Allows the two T1 payloads to be monitored.
Craft (RS-232) port	Provides bidirectional communication between the unit and an external terminal to allow configuration and performance monitoring through the Maintenance Terminal screens.
CLEI and ECI bar code label	Provides the human-readable Common Language Equipment Identifier (CLEI) code number and the Equipment Catalog Item (ECI) bar code number.

Front Panel 150-319-155-04, Revision 04

Table 2 lists the front-panel display messages. The four-character displays reports the code of a pertinent alarm, loopback or diagnostic message, in some cases followed by a second four-character message that modifies the first message with a value or current configuration setting.

Table 2. Front-panel Display Messages

Message	Full Name	Description
ALARM MESSAGES		
ACO	Alarm CutOff	A system alarm has occurred, and has been retired to an ACO condition by pressing the SEL button on the HLU front panel.
ALRM	Alarm Condition	A system alarm condition is in effect.
BER	Bit Error Rate	A system BER alarm is in effect.
LLOS	Local Loss of Signal	Indicates that no signal is detected at the T1 input to the HLU. Causes a system alarm.
LOSW	Loss of Sync Word	Indicates that one of the HDSL loops has lost sync. Causes a system alarm.
MAL1 or MAL2	Margin Alarm Loop 1 or Loop 2	The margin on HDSL Loop 1 or Loop 2 has dropped below the threshold (1 to 15 dB) as set by the operator.
RLOS	Remote Loss of Signal	Indicates that no signal is detected at the DS1 input to the HRU. Causes a system alarm.
LOOPBACK MESSA	IGES	
CDU <i>n</i> ?	Customer Doubler <i>n</i> Loopback	Query to initiate loopback at doubler n to Customer Installation (CI), where n is the number of the doubler.
CLOC	Customer Local Loopback	Signal from customer is looped back to the customer at the HRU.
CREM	Customer Remote Loopback	Signal from customer is looped back to the customer at HLU-319.
NDU <i>n</i> ?	Network Doubler <i>n</i> Loopback	Query to initiate loopback at doubler n to network, where n is the number of the doubler.
NLOC	Network Local Loopback	DSX-1 signal is looped back to DSX-1 at the HLU.
NREM	Network Remote Loopback	DSX-1 signal is looped back to DSX-1 at the HRU.
SMJK	Remote SmartJack Loopback	Signal from DSX-1 is looped back at the HRU by the HRU SmartJack module.
DIAGNOSTIC MESS	SAGES	
1= <i>xx</i> or 2= <i>yy</i>	HDSL Loop Margins	Indicates the power of the received HDSL signal on each loop relative to noise. Any value of 06 (dB) or greater is adequate for reliable system operation.
ACQ1 or ACQ2	Acquisition 1 or Acquisition 2	The multiplexers of the HLU and the HRU or first doubler are trying to establish synchronization over Loops 1 or 2 of Span 1.
A <i>n</i> L1 or A <i>n</i> L2	Acquisition <i>n</i> Loop 1 or Acquisition Loop 2	The multiplexers of the two devices on Span n are trying to establish synchronization with each other on Loops 1 or 2, where n is the number of the span.
ARM	HiGain System Armed	Armed to respond to Intelligent Repeater Loop Codes.
BAD RT?	No response from HRU	The HLU does not receive any response from the HRU. Therefore, the integrity of the HRU or the two HDSL loops (they may be open) is questionable.
CODE xxxx	Line Code: AMI, B8ZS	The line code mimics either of the two DS1 line code settings, Alternate Mark Inversion (AMI) or Bipolar with 8-zero Substitution (B8ZS). Displayed during System Settings review mode.
DS0	DS0 Blocked Channels	Indicates status of DSO blocked channels. NONE indicates no channels are blocked. BLK indicates some channels are blocked.

150-319-155-04, Revision 04 Front Panel

 Table 2.
 Front-panel Display Messages (Cont.)

Message	Full Name	Description
FERR	Framing Bit Error	Framing bit error occurred at HLU T1 input.
FRM xxxx	Frame: SF, ESF, UNFR, NONE	Defines the type of frame pattern being received from the DSX-1: SuperFrame (SF), Extended SuperFrame (ESF), Unframed (UNFR), or NONE. Displayed during System Settings review mode.
H1ES or H2ES	HDSL Cyclic Redundancy Check (CRC) Error Channel 1 or Channel 2	HDSL Loop 1 or Loop 2 CRC error.
<i>n</i> HDU	Number of Doublers	This message indicates the number (n) of doublers in the circuit.
INSL, then xxDB	Maximum Insertion Loss	The maximum Insertion Loss message (INSL) appears followed by xxDB, where xx is the maximum insertion in dB of all spans and loops.
LBPV	Local Bipolar Violation	A bipolar violation has been received at the T1 input to the HLU-319.
LIST xxxx	HLU-319 List Number	The software list number (xxxx) appears during the System Settings review mode. Press the MODE button for 3 seconds to display the list number.
MNGD	Managed	The HLU is under control of the HMU-319 network management unit. In this state, the front-panel craft port and push buttons are disabled.
PWR FEED GND	Power Feed Ground	One of the HDSL loops has been grounded.
PWR FEED ON	Power Feed On	Indicates that the HDSL loops are not grounded or shorted.
PWR FEED OFF	Power Feed Off	HDSL span power has been turned off by setting the PWFD option to DIS, or HDSL span power has been turned off by use of the A1LB/A2LB/A5LB Intelligent Office Repeater (IOR) Power Down code.
PWRF SHRT	Power Feed Short	Indicates a short between the two HDSL pairs. This same message can occur with an HRU that is drawing the correct amount of power over good cable pairs but cannot communicate with the HLU.
SELF TEST	Self Test	The HLU is in a self-test mode. This occurs every power On/Off cycle.
SIG1 or SIG2	Signal 1 or Signal 2	The transceivers of the HLU and HRU or first doubler are trying to establish contact with each other on Loop 1 or Loop 2 of Span 1.
S <i>n</i> L1 or S <i>n</i> L2	Signal <i>n</i> Loop 1 or Loop 2	The transceivers of the two devices on Span n are trying to establish contact with each other on Loop 1 or Loop 2, where n is the number of the span.
TLOS	Transmit Loss of Signal	DSX-1 signal is looped back to the DSX-1 interface at the HRU. HRU is in a logic loopback state caused by a loss of its DS1 input from the CI, if enabled at the HRU by its TLOS switch option.
VER xxxx	HLU-319 Version Number	The software version number (xxxx) appears during the System Settings review mode. Press the MODE button for 3 seconds to display the software version.

Installation 150-319-155-04, Revision 04

INSTALLATION



Upon receipt of the equipment, visually inspect the contents for signs of damage. If the equipment has been damaged in transit, immediately report the extent of damage to the transportation company and to PairGain Technologies.




Figure 2. Installing the HLU-319 into a Shelf



When installing an HLU in a chassis, be sure to wear an antistatic wrist strap. Avoid touching components on the circuit board.

- 1 Slide the HLU-319 into the card guides for the desired slot, then push the unit in until it touches the backplane card-edge connector (Figure 2).
- 2 Place your thumbs on the HLU-319 front panel and push the HLU-319 into the card-edge connector until it is entirely within the card guides. This indicates that the card is properly seated.

150-319-155-04, Revision 04 Installation

VERIFICATION

Once the HLU-319 is installed, verify that it is operating properly. To do this, you need to monitor the following:

- Status LED
- Status messages reported by the front-panel display (see Table 2 on page 6)

Verification without a Downstream Device

If there is no downstream device installed:

- 1 Verify that the HLU powers up. (The front-panel display illuminates and reports four-character status messages. See Table 2 on page 6 for a list of messages.)
- 2 Verify that the HLU attempts to communicate with downstream devices. Even if a downstream device is not present, the following events should occur:
 - **a** The front-panel display reports four-character status messages.
 - **b** The HLU enters self-test mode (Status LED is yellow).
 - c The HLU again attempts communication with downstream devices, repeating events a through b until a downstream device is detected.

Verification with a Downstream Device

If a downstream device has been installed:

- 1 Verify the HLU powers up. (The front-panel display illuminates and reports status messages.)
- 2 Verify the HLU attempts to communicate with downstream devices (status LED flashes green). One of the following occurs:
 - If downstream devices are successfully identified and the HDSL loops synchronize, the HLU status LED will be a steady green. The HLU reports normal margin messages on the front-panel display.
 - If downstream devices are not successfully identified, the HLU reports four-character status messages and enters self-test mode. The HLU successively:
 - enters self-test mode
 - completes self-test mode
 - attempts communication again
 - reports four-character status messages

The HLU repeats this cycle until a downstream device is detected.

- **3** If there is more than one span, verify that each subsequent span synchronizes normally by monitoring the front-panel display messages.
- 4 If a remote unit is installed, verify that the last span synchronizes normally. The HLU status LED should be a steady green, and the front-panel display should report normal margin messages.
- 5 Verify that a valid T1 signal has been applied to the HLU and the HRU.
 - If no T1 signal is being applied to either the HLU or the HRU inputs, then the appropriate T1 alarms (LLOS or RLOS) are observed on the front-panel display and the status LED flashes red.
 - If a valid T1 signal is being supplied to the HLU and HRU, then T1 alarm indications should be absent and the status LED should be a steady green.

Installation 150-319-155-04, Revision 04

PROVISIONING REQUIREMENTS

Refer to "Provisioning" on page 11 for information about using the MODE and SEL buttons or the Maintenance Terminal screens to configure the HLU. While the MODE and SEL buttons can be used to manually accomplish some provisioning tasks, such as setting system options, the Maintenance Terminal screens (available when you connect a PC to the craft port) can handle all provisioning tasks. Tasks that you need to complete are:

- 1 Set the time and date (see "Set Clock Screen" on page 19).
- 2 Set the circuit IDs (see "View System Inventory Screen" on page 36).

Assuming that the HLU has been successfully installed and provisioned, you should do the following to ensure an accurate Alarm History and Performance History.

- 1 Clear the Span Status, Performance Data, and Performance History screens. This can be accomplished by pressing C (clear) at the Span Status screen (see "View Span Status Screen" on page 15).
- 2 Clear the Alarm History screens (see "View Alarm History Screen" on page 34).

PROVISIONING

This is a reference section for HLU provisioning. There are two methods for provisioning the HLU-319 List 5E:

- Use the MODE and SEL buttons on the front panel of the HLU to:
 - set system options
 - reset the HLU to its factory default settings for system options
 - display system option settings (scroll mode)
 - select system loopbacks
- Use a maintenance terminal (ASCII terminal or a PC running terminal emulation software) connected to the HLU craft port to access the Maintenance Terminal Main Menu (Figure 3 on page 14). This gives you full access to all HLU status, history, inventory, and provisioning screens.



No dip switches or jumpers are required to provision the HLU-319 as it contains a Non-volatile Random Access Memory (NVRAM) which stores the system option settings. System option settings are retained if shelf power is lost or if the HLU-319 is unplugged.

Using the MODE and SEL Buttons

Setting Options through MODE and SEL

To provision the HLU-319 List 5E through the MODE and SEL buttons on the front panel:

- Press the MODE button for 2 seconds and then release it. The front-panel display alternately shows the first system parameter and its current setting.
- 2 Press the SEL button to step through all possible settings (one at a time) of the selected parameter.
- 3 After the desired setting has been selected, press the MODE button. This updates the current displayed parameter to the selected setting, and then advances to the next configurable parameter. After the last parameter has been selected, a CONF NO message appears on the front-panel display.
- 4 Do one of the following:
 - To cancel the session without saving the requested parameter changes, press the MODE button or, do nothing. (After 30 seconds, the display returns to its normal mode without saving the new changes.)
 - To accept the requested parameter changes, press the SEL button. (A CONF YES message displays, and the display returns to its normal mode after saving the new changes.)

Resetting to Factory Default Values

All user options (Table 8 on page 21) can be set to the factory default values using the MODE and SEL buttons. To set the user options to their default values:

1 Press the SEL button for 6 seconds until the following message appears:

DFLT NO

2 Press the SEL button while the DFLT NO message is displayed.

The message changes to DFLT YES indicating the factory default values are now in effect and the display returns to the normal mode.

To terminate the DFLT mode without setting the factory default values, do one of the following:

- Press the MODE button to return to the normal display mode
- Wait 30 seconds for the unit to return to the normal display mode.

Displaying System Parameter Settings

To scroll through the current settings of all system parameters, press the MODE button for 3 or more seconds. The following parameters are displayed:

- HLU software version number
- HLU List number
- Type of frame pattern being received from the DSX-1
- Line code of the signal being received from the DSX-1 (see note)
- HDSL power level setting
- All user-configured parameter settings

Disabling an Alarm

If the system is in a Minor alarm state, the alarm relay can be disengaged by pressing the SEL button. This turns off the Alarm Cut-off (ACO) indication.

Loopback Modes

See "Loopback Operation" on page 44 for instructions on using the MODE and SEL buttons to activate loopbacks.

USING A MAINTENANCE TERMINAL

Connecting to a Maintenance Terminal

The craft port on the front panel allows you to connect the HLU-319 to a maintenance terminal (ASCII terminal or PC running a terminal emulation program). Once connected to a maintenance terminal, you can access the maintenance, provisioning, and performance screens.

To connect to a maintenance terminal:

- 1 Connect a standard 9-pin terminal cable to the RS-232 craft port (Figure 1 on page 4) on the HLU-319 front panel.
- 2 Connect the other end of the cable to the serial port on the maintenance terminal.
- 3 Start a terminal emulation program such as ProComm (emulating a VT-100 terminal).
- 4 Configure the maintenance terminal to the following communication settings:
 - 1200 to 9600 baud (9600 baud is recommended)
 - no parity
 - 8 data bits
 - 1 stop bit
 - hardware flow control to OFF
- 5 Press the **SPACEBAR** several times to initiate the autobaud connection and to initialize the Maintenance Terminal screens.

Accessing the Maintenance Terminal Screens

The following sections describe how to use the Maintenance Terminal screens to view, provision and diagnose an HLU-319 List 5E system.

Navigation Keys

Table 3 lists keys you can use on the maintenance terminal to navigate the Maintenance Terminal screens.

Table 3. Navigational Keys on the Maintenance Terminal

Key	Function
Α	Automatically updates the screen data
U	Updates screen data
C	Clears screen data
S	Selects the next Span Status screen (for doubler applications)
1, 2, 3, 4, or 5	Selects a specific Span Status screen (for doubler applications)
P	Selects the previous page of screen data
N	Selects the next page of screen data
E	Exits the current screen
L	Selects the Loopback menu from the Troubleshooting screen
В	Returns to the main Troubleshooting screen from the Troubleshooting (H)elp, (M)argin Values or (I)nsertion Loss screens

Maintenance Terminal Main Menu

Figure 3 shows the Maintenance Terminal Main Menu from which you can access system administration screens. The function of each screen selection is listed in Table 4. To access a screen, type the letter shown next to the menu item.

```
HIGAIN HLU-319 MAINTENANCE TERMINAL MAIN MENU (ver V7.2L-5E)
CIRCUIT ID#:

A. VIEW SPAN STATUS
B. SET CLOCK
C. SYSTEM SETTINGS
D. LOOPBACK MODE: NONE
E. VIEW PERFORMANCE DATA
F. VIEW PERFORMANCE HISTORY
G. VIEW ALARM HISTORY
H. VIEW SYSTEM INVENTORY
I. VIEW TROUBLESHOOTING
```

Figure 3. Maintenance Terminal Main Menu

Table 4. Maintenance Terminal Screens

Press Key	To View Screen	Screen Description	See page:
Α	View Span Status	Provides access to subscreens that allow you to monitor the HDSL and T1 line status between the HLU and the HRU.	15
В	Set Clock	Allows you to set both the time and the date parameters at the HLU, and to update the same settings at the HRU.	19
C	System Settings	Allows you to set all user options.	20
D	Loopback Mode	Provides access to a subscreen that allows you to enable and disable loopbacks at both the network and customer side.	26
E	View Performance Data	Provides access to subscreens that allow you to view the Errored Seconds (ES) and Unavailable Seconds (UAS) between the HLU and the HRU in 15-minute intervals over a 4-hour time period per screen for a total of 24 hours (6 screens).	29
F	View Performance History	Provides access to subscreens that allow you to view the ES and UAS between the HLU and the HRU in 24-hour intervals over a 31-day period.	31
G	View Alarm History	Provides access to subscreens that allow you to view alarm conditions between the HLU and the HRU.	34
H	View System Inventory	Allows you to enter a unique circuit ID (up to 24 alpha-numeric characters).	36
	View Troubleshooting	Provides a graphical analysis of the circuit and identifies problem areas	38

Selecting a Maintenance Terminal Function

To perform a function within the Maintenance Terminal screens, you can:

- Press the key indicated to the left of the selection.
- Press the letter in parenthesis for the parameter to be changed.

System Spans

As shown in Figure 4, the HLU can support up to four doublers with five HDSL spans. The Span Status, Performance Data, and Performance History may display as many five screens to depict an HLU-319 List 5E system.




Figure 4. System Spans

USING THE MAINTENANCE TERMINAL SCREENS

View Span Status Screen

The View Span Status option allows you to view up to five system status screens that provide information about the HDSL Loop 1, HDSL Loop 2, and the DS1. For doubler applications, the available Span Status screens depend on whether the system includes one, two, three, or four doublers.

Press A from the Maintenance Terminal Main Menu to open the Span Status screen (Figure 5 on page 16). If no doubler (HDU) is present, the screen reports span status for the subscriber lines between the HLU and the HRU.

If there are additional doublers, the Span Status screen reports status on each span. Figure 6 on page 16 shows status between HDU4 and the HRU in a system with four doublers. See Table 5 on page 17 for an explanation of the Span Status fields.

From each Span Status screen you can:

- Press C to clear the cur (current), min (minimum) and max (maximum) numeric counts. This also clears the Performance History and Performance Data screens.
- Press A to automatically update status screens. (Press A again to turn off auto update.)
- Press **U** to update cur (current) values.
- Press s to view the next available span (for doubler applications).
- Press E to exit and return to the previous screen.
- Press 1, 2, 3, 4, or 5 to select a specific span (for doubler applications).

Span Status Screen without Doublers




Figure 5. Span Status Screen: No Doubler

Span Status Screen for Doubler Applications

If doublers have been added, status is also reported for these. Span Status can have up to five screens, depending on the number of HDUs.




Figure 6. Span Status Screen: Four Doublers (Span 5)

Table 5 lists the Span Status fields and descriptions. Table 6 and Table 7 on page 18 describe alarm and loopback messages displayed on the Span Status screens.

Table 5. Span Status Fields and Descriptions

Span Status Field	Description		
Time	Time of day when Span Status was checked.		
Date	Date when Span Status was checked.		
Circuit ID#	Shows the user-defined circuit ID.		
Alarms	Presence or absence of alarm conditions. See Table 12 on page 42.		
Loopback	Indicates Off condition or identifies specific active loopback. See Table 13 on page 45.		
Power Level	Indicates the HDSL line voltage in its Low (-140 Vdc) or High (±112 Vdc) state.		
Margin	Indicates the excess signal to noise ratio at all HDSL ports, relative to a 10 ⁻⁷ Bit Error Rate.		
	First value is current margin.		
	 Second value is minimum margin since last cleared. 		
	Third value is maximum margin since last cleared.		
	 N/A means that the margin is not available. 		
	The minimum and maximum margins are cleared and updated every time the Span Status screen is cleared and every time the system clock passes 12:00 AM midnight.		
Pulse ATTN	Indicates the attenuation of the 2B1Q pulse from the distant end. The value is related to the 196 kHz loss of the cable pair. The pulse attenuation is a more direct indication of the loop attenuation to the 2B1Q signal than is the 196 kHz loss. The normal HiGain ATTN operation range is from 0 to 28 dB.		
INS Loss	Indicates the approximate insertion loss of the loops at the HDSL line rate of 196 kHz. It is generated by multiplying the pulse attenuation by 1.25. Normal range is 0 dB to 35 dB.		
24-Hour ES	The number of one second intervals that contained at least one CRC error. This value is a running total of the last 24 Hours.		
24-Hour UAS	The number of seconds the HDSL loop was out of sync.		
24-Hour ES Count	The number of seconds in which at least one error was detected on the DS1 input over a 24-hour period. Errors included are: DS1 Frame errors; BPV and ESF CRC errors.		
24-Hour UAS Count	The number of seconds during which the DS1 input signal was absent (175 \pm 75 consecutive zeroes) over a 24-hour period.		
Frame type	Type of DS1 framing used on the input stream (SF, ESF, Unframed or No Activity).		
Code type	Type of DS1 line coding used (AMI, B8ZS, AMI: ZBTSI, or B8ZS: ZBTSI). The latter two indicate the code type that is being received when HiGain line is set to ZBTS1 mode. When set to AMI or B8ZS, the HLU displays the selected code rather than the code type that is actually being received.		



The Span Status screens shown on the previous page display a four-character code under the Alarms entry. These codes are described in Table 6 on page 18.

The following codes are reported with a RCV or XMT prefix that indicates the signal is being transmitted or received: LLOS, RLOS, LAIS, or RAIS.

RCV (xxxx) - Signal received (xxxx) at the T1 input to either the HLU or HRU.

XMT (xxxx) - Signal transmitted (xxxx) at the T1 output of either the HLU or HRU.

 Table 6.
 HDSL System Alarms

Message	Name	Description
BER	Bit Error Rate	The Total System Error Count (TSEC) has exceeded the user-selected threshold.
LOSW	Loss of Sync Word	One of the HDSL loops has lost synchronization.
LLOS	Local Loss of Signal	No signal from HLU-319 List 5E local T1 input.
MAL1 or MAL2	Margin Alarm 1 or Margin Alarm 2	The margin on the HDSL Loop 1 or Loop 2 has dropped below the threshold (1 to 15 dB) set by the user. Setting the threshold to zero inhibits the margin alarm.
NONE	No Alarm	No alarm is indicated.
RAIS or LAIS	Remote (or Local) Alarm Indicating Signal	Indicates an AIS pattern of all ones is being transmitted from the remote (or local) T1 output port.
XMT-YELW	Transmit Yellow	A yellow alarm is being transmitted at the T1 output of the HLU-319.
XMT-IDLE	Transmit Idle	An idle pattern (7E) is being transmitted at the T1 output of both the HLU-319 and HRU-402. This response is only available when the LPBK option is set to ENFT and HLU-319 is connected to an HRU-402.
RLOS	Remote Loss of Signal	Indicates that no signal is detected at the DS-1 input to the HRU.

Table 7 lists loopback messages displayed on the Span Status screens. For information about loopback codes, see "GNLB Test Procedures" on page 48.

 Table 7.
 Loopback Messages

Message	Full Name	Description
ARM	Armed	The HiGain system has detected the Intelligent Repeater (IR) loopback arming code (2-in-5).
CDU <i>n</i>	Customer Doubler <i>n</i> Loopback	Loopback at Doubler (n) to CI initiated by an Intelligent Line Repeater (ILR) code, the MODE and SEL buttons on HLU-319 List 5E front panel, or by the maintenance terminal.
CHREV-SPx	Channels Reversed	The Loop 1 and Loop 2 HDSL pairs are reversed at Span x. Loop 1 is specified to carry the (-) simplex DC voltage, and Loop 2 is specified to carry the (+) simplex DC voltage. SPx indicates that the first occurrence of a reversed span is on Span x, where x is the number of the span.
CLOC	Customer Local Loopback	Loopback at HRU (local) to CI initiated from Customer Premises Equipment (CPE) by the ILR #2 code, the MODE and SEL buttons on the HLU-319 front panel, or by the maintenance terminal.
CREM	Customer Remote Loopback	Loopback at HLU-319 (remote) to customer initiated by Intelligent Office Repeater (IOR) code, the MODE and SEL buttons on the HLU-319 front panel, or by the maintenance terminal.
(HG)	HiGain	The loopback was initiated from a HiGain front panel or by a HiGain maintenance terminal loopback command.
NDU <i>n</i>	Network Doubler <i>n</i> Loopback	Loopback at Doubler (<i>n</i>) to network initiated by ILR code, by the MODE and SEL buttons on the HLU-319 front panel, or by the maintenance terminal.
NLOC	Network Local Loopback	Loopback HLU-319 (local) to network initiated from CO by IOR code, the MODE and SEL buttons on the HLU-319 front panel, or by the maintenance terminal.

 Table 7.
 Loopback Messages (Cont.)

Message	Full Name	Description
NREM	Network Remote Loopback	Loopback at HRU to network initiated from CO (network) by ILR #2 code, the MODE and SEL buttons on the HLU-319 front panel, the HRU manual loopback button, or by the maintenance terminal.
OFF	Off	No active loopback mode.
(PL)	Pay Load	The loopback was initiated by a command that was embedded in the T1 data path.
SMJK	SmartJack Loopback	Loopback from HRU to network initiated by (2-in-5) inband loopback code or out-of-band ESF data link code.
TLOS	Transmit Loss of Signal Loopback	HRU is in a logic loopback state caused by a loss of its T1 input from the CI (if enabled at the HRU through its TLOS switch option).

Set Clock Screen

Press B at the Maintenance Terminal Main Menu to open the Set Clock screen (Figure 7).




Figure 7. Set Clock Screen



All time information is lost when power is removed. The last date, however, is retained in NVRAM and reappears when power is restored.

Set Time

The cursor defaults to the New Time field. To set the system time, type the hour and minute in the 24-hour format of **hh:mm:ss** (setting the seconds is optional), then press **ENTER**. The New Date field appears.

Set Date

To set the system date, type the month, day and year in a **mm/dd/yy** format, then press **ENTER**. The Update Remote field appears.



When editing entries in the Set Clock screen and when using the Terminal emulation program in Windows 3.1, pressing the BACKSPACE key deletes two characters instead of just one.

Update the HRU Time and Date

The remote unit date and time is set by using this option. Do one of the following:

- Press U to update the HRU to the same date and time set for the HLU-319 List 5E.
- Press **ENTER**. (The date and time are not updated.)

System Settings Screen

The options set from the System Settings screen are the same as the options set through the HLU-319 Mode and SEL buttons on the front panel. The exceptions are Margin Alarm Threshold and DS0 Blocking, which can only be set at this screen. Refer to Table 8 on page 21 for a listing of system setting options. Press **C** at the Maintenance Terminal Main Menu to open the System Settings screen (Figure 8).

```
SYSTEM SETTINGS
TIME: 12:46:06
DATE: 09/15/99
                                       CIRCUIT ID#:
A. EQUALIZATION...: 0
                                         P. MARGIN ALARM THRESH : 4
B. SMARTJACK LPBK.: ENABLED
                                         Q. RLOS (DS1 LOS) ALARM: ENABLED
C. SPECIAL LPBK....: GNLB
                                         R. ALARM PATTERN....: AIS
F. POWER..... AUTO
                                         S. REMOTE PROVISION....: ENABLED
G. ZBTSI..... OFF
                                         T. BPVT....: DISABLED
H. BER ALARM THRESH: NONE
                                         U. CDI.....: DISABLED
I. LOOPBACK TIMEOUT: 120
J. ALARM....: DISABLED
K. DS1 LINE CODE...: B8ZS
L. FRAMING....: AUTO
M. AIS ON HDSL LOSW: 1 LOOP
N. AIS ON SMJK/NREM: ENABLED
                   O. DSO BLOCKING: xx = Blocked Channels
   01 \ 02 \ 03 \ 04 \ 05 \ 06 \ 07 \ 08 \ 09 \ 10 \ 11 \ 12 \ 13 \ 14 \ 15 \ 16 \ 17 \ 18 \ 19 \ 20 \ 21 \ 22 \ 23 \ 24
                             (D)efaults, (E)xit
                 Enter the option letter to change setting
(C)onfirm
```

Figure 8. System Settings Screen

You have the following options at the Systems Settings screen:

- Press the desired option letter to change that setting.
- Press **D** to set all user options to the factory default values.
- If changes were made, press **C** when exiting to confirm, or press any other key to ignore changes.
- Press **E** to exit and return to the main menu.

Table 8 describes the System Settings options and lists the corresponding front-panel display codes. Factory default parameters appear in boldface type.

Table 8. HLU-319 List 5E System Settings Options

System Settings Screen Options	Front Panel Display Code	Selection	Description
Equalization	EQL	0	Sets the equalizer to DSX-1 for 0 - 132 feet.
		133	Sets the equalizer to DSX-1 for 133 - 265 feet.
		266	Sets the equalizer to DSX-1 for 266 - 398 feet.
		399	Sets the equalizer to DSX-1 for 399 - 532 feet.
		533	Sets the equalizer to DSX-1 for 533 - 655 feet.
SmartJack Lpbk	LPBK	DIS	Configures the HiGain system to ignore all in-band SmartJack loopback commands.
		ENA	Enables the HiGain system to recognize all in-band SmartJack loopback commands. CDI option is disabled when ENFT is set.
		ENFT	Enables the HLU-319 to respond to the DDS latching loopback commands required for fractional T1 applications.
Special Lpbk	SPLB	GNLB	Configures the HiGain system to respond to the generic (3/4-in-7) in-band loopback codes.
		A1LB A2LB	Configures the HiGain system to respond to the in-band loopback codes of the Teltrend addressable repeater.
		A3LB	Configures the HiGain system to the in-band loopback codes of the Wescom addressable repeater.
		A4LB	Configures the HiGain system to respond to the in-band loopback codes of the Wescom Mod 1 addressable repeater.
		A5LB	Configures the HiGain system to respond to the in-band loopback codes of the Teltrend Mod 1 addressable repeater.
Power (see "HDSL Line Voltage Options" on page 26).	PWRF	DIS	Disables power to the High-bit-rate Digital Subscriber Line (HDSL) pair.
		LOW	Keeps the HDSL line voltage at -140 V maximum for all applications.
		AUTO	Allows the HDSL line voltage to automatically switch between -140 V maximum for non-doubler applications and ± 112 V for doubler applications.
		HIGH	Forces the HDSL line voltage to $\pm 112~V$ for all applications.
Zero-Byte Timeslot Interchange	ZBTSI	OFF	Instructs the HiGain system that the Extended Superframe (ESF) frame is operating in its normal non-Zero-Byte Timeslot Interchange (ZBTSI) mode.
		ON	Instructs the HiGain system that the ESF frame is operating in its ZBTSI mode.
BER AlarmThresh	BERT	NONE	Prevents generation of a system alarm due to excessive BER.
		1E-6	Flashes the red STATUS LED when the BER alarm threshold exceeds 10 ⁻⁶ .
		1E-7	Flashes the red STATUS LED when the BER alarm threshold exceeds 10^{-7} .

 Table 8.
 HLU-319 List 5E System Settings Options (Cont.)

System Settings Screen Options	Front Panel Display Code	Selection	Description
Loopback Timeout	LBT0	NONE	Disables automatic timeout cancellation of all loopbacks.
		20	Sets automatic cancellation of all loopbacks to 20 minutes after initiation.
		60	Sets automatic cancellation of all loopbacks to 60 minutes after initiation.
		120	Sets automatic cancellation of all loopbacks to 120 minutes after initiation.
Alarm	ALM	DIS	Opens the system alarm relay contacts if closed, and disables activation of the system alarm relay when a system alarm condition occurs.
		ENA	Enables activation of the system alarm relay when a system alarm condition occurs.
DS1 Line Code	DS1	B8ZS	Places both the HLU-319 and HRU into the B8ZS mode.
		AMI	Places both the HLU-319 and HRU into the AMI mode.
Framing	FRMG	AUTO	Configures the HiGain system to operate in an Auto-Framing (AUTO) mode in which it continuously searches the input DS1 bit stream for a valid SF or ESF frame pattern. This feature is required for fractional T1 applications (DS0 blocking) where it insures proper channel time slot alignment. It is recommended that the Unframed (UNFR) mode be used for all unframed applications to avoid syncing on data patterns that "look" like frame sequences.
		UNFR	Configures the HiGain system to operate in an unframed mode. This mode disables the auto framing process and forces the HiGain system to function as a transparent bit pipe.
AIS on HDSL LOSW (see "HAIS Option" on page 25).	HAIS	2LP	Transmits the Alarm Indicating Signal (AIS) at both the HLU-319 and HRU DS1 output ports when both of the HDSL loops are not in sync (LOSW).
		1LP	Transmits the AIS at both the HLU-319 and HRU DS1 output ports when either of the two HDSL loops is not in sync or if a margin alarm occurs.
AIS On SMJK/NREM	SAIS	DIS	Transmits the network signal towards the CI RCV port or to open and terminate its CI RCV port when an HRU Network Remote Loopback (NREM) or SmartJack Loopback (SMJK) is executed. The AIS is not sent towards the CI.
		ENA	Transmits the AIS towards the CI RCV port when in NREM, SmartJack, or loopback conditions.
DSO Blocking	DSO	BLK	The Digital Signal, Level 0 (DS0) blocking option can only be set with a maintenance terminal connected to the craft port. The front panel four-character display only displays the status of the blocking option. BLK indicates at least one channel is blocked (see "DS0 Blocking Option" on page 24).
		NONE	Indicates no channels are blocked.
Margin Alarm Thresh	MARG	0 to 15 dB	The margin alarm threshold can only be set with a maintenance terminal connected to the craft port. It determines the minimum allowable margin below which a system alarm can occur. Zero disables the alarm (see "Margin Alarm Threshold Option" on page 25).
		4dB	Default Value.

 Table 8.
 HLU-319 List 5E System Settings Options (Cont.)

System Settings Screen Options	Front Panel Display Code	Selection	Description
RLOS (DS1 LOS) Alarm	RDA	DIS	Prevents a remote DS1 LOS condition at the input to the HRU from causing an LOS alarm. The front panel Status LED still flashes red, the ALRM Remote Loss of Signal (RLOS) message is displayed, and LOS is sent towards the network from the HLU instead of AlS.
		ENA	Enables a remote DS1 LOS condition at the input to the HRU to generate an LOS alarm. AIS or Loss of Sync (LOS) (depending on the ALMP setting) is sent towards the network.
Alarm Pattern	ALMP	AIS	Enables HiGain to output an AIS payload at its DS1 ports for LOSW, DS1 LOS, and margin alarms.
		LOS	Enables HiGain to output an LOS condition at its DS1 ports for LOSW, DS1 LOS, and Margin alarms.
Remote Provision	RTPV	DIS	Prevents options from being changed at the remote when remotely logged on
		ENA	Allows options to be changed at the remote when remotely logged on.
BPVT (BPV Transparent)	BPVT	DIS	Disables input DS1 BPVs and HDSL CRC errors from being converted into DS1 BPVs at the distant end's DS1 output port.
		ENA	Enables input DS1 BPVs and HDSL CRC errors to be converted into DS1 BPVs at the distant end's DS1 output port. This makes HiGain transparent to BPVs and enables fast LOSW.
CDI (Customer Disconnect Indicator)	CDI	DIS	Enables the HLU to output the special payload patterns that indicate a RLOS condition.
		ENA	Disables the CDI output patterns.
Confirm Setting	CONF	YES	Confirms that all operating modes are to be updated to their current selections.
		NO	Prevents the most recently selected operating mode selections from being updated. They remain as they were before the system option settings mode was entered.

Equalization Option

Equalization is the configuration of system transmission characteristics within specified limits. An adaptive equalizer inserts a frequency-shaped loss that corresponds to an equivalent addition of an appropriate cable length. By simulating the additional cable loss necessary for correct operation, the equalizer compensates for a range of variation in transmission path characteristics.

BPVT Option

The HLU-319 List 5E improves HiGain's compatibility with Digital Loop Carrier (DLC) feeder applications because of its ability to transmit T1 BPV occurrences between its T1 interfaces. This feature is required to support protection switching in DLC applications. Each DLC terminal must be able to monitor the integrity of its Receive T1 payload and then switch to the protected line when the integrity of the path drops below specific user-selected limits. An essential requirement of this feature is the need for each DLC terminal to detect BPVs in its T1 input. Standard HDSL systems correct T1 BPVs at the input and therefore prevent them from being detected by the DLC terminals to which they are connected. The HLU-319 and its associated remote units remove this limitation and become BPV transparent by detecting and counting input BPVs at each end and then replicating them at the T1 output port of the distant end.

This BPVT option is controlled by the BPVT user option, which allows it to be Enabled (ENA) or Disabled (DIS).



When BPVT is enabled in systems with four or less doublers, the response time to an HDSL LOSW is approximately 70 ms, which gives DLC terminals time to react and avoid dropped calls.

In addition, the CRCs in each direction of every HDSL loop of each span are also counted and added in with the BPV count to produce a Total Error Count (TEC) that indicates the integrity of both the T1 and HDSL paths. A TEC in each direction is calculated each second by adding the number of BPVs to the number of HDSL CRCs in that direction. The maximum TEC count is 12000. This TEC number is converted into BPVs at the distant end during the following second at a rate of 1 BPV every 128 T1 bits up to a maximum of 12000 (BER=7.7 x 10⁻³). This maximum rate is more than adequate since it exceeds the maximum 10⁻³ BER required by most DLC systems.

BER Option

The BER option also uses this (BPV/CRC) TEC to generate an Alarm if enabled. The HLU combines the 1-second TEC counts in both directions for the last 60 seconds. It uses this 1-minute Total System Error Count (TSEC) to generate an alarm if it exceeds the selected BER threshold of (1E-6 or 1E-7) as follows:

- BER option = 1E-6. Alarm is generated if TSEC > 92
- BER option = 1E-7. Alarm is generated if TSEC > 9

Once initiated, the alarm clears when the TSEC drops below its associated threshold count. For dribbling errors, the alarm can come and go in intervals as short as 1 second. Alarms due to bursty impulse noise transients usually require the full 60 seconds or longer to clear depending on the frequency of the transients. This BER option is always present in any line unit circuit since it is independent of other versions of HiGain modules in the circuit. When connected to an HRU, other than the HLU-402, HLU-406, or HLU-411, only the BVPs detected by the HLU are included in the TBC. The BPVs at the HRU are not counted.

DS0 Blocking Option

To set the DS0 Blocking option from the Main screen:

- 1 Press **c** to select the Systems Settings screen (see Figure 8 on page 20).
- 2 Press of for the DS0 blocking selection. The DS0 channels are blocked or unblocked by entering each channel number. Multiple channels can be selected by inserting a space between each entry.
- 3 After all the new settings have been made, press **C** to (Confirm) and then **E** for (Exit). The new choices are now installed.

If DS0 blocking is invoked in a HiGain system that has an earlier version HRU that does not support the blocking option, blocking only occurs at the DSX-1 output of the HLU-319 List 5E. The HRU DS1 output is not blocked. Also, all blocked channels are temporarily unblocked for all HiGain system loopback tests for all DS1 blocking settings. This allows the standard full bandwidth T1 loopback tests to be performed for all DS0 blocking settings.

If any of the unused DS0 channels of a fractional T1 service are filled with information other than an idle code of all ones, the HiGain system blocks this information from reaching the remote end of the circuit and replaces those DS0 channels with an idle code of all ones.

Blocking the idle code results in a mismatch between the CRC checksum delivered to the remote end (when the payload is in the ESF format) and the checksum calculated by the remote T1 Channel Service Unit (CSU). This implies that errors are being made on the loop when actually the blocking function created the CRC errors. Enabled DS0 channels pass error-free.

In order to avoid this condition, fractional T1 customers should fill the unused time slots with an idle code. This is a common capability on Fractional T1 CSU/DSU, D4 channel banks, and other CPE devices capable of connecting to Fractional T1 service.

DS1 Line Code Option

The DS1 line code option should always be set to conform to the type of DS1 service (AMI or B8ZS) being provided by the HiGain system. The AUTO mode, which can adapt to either AMI or B8ZS, should only be used in applications that require it (such as when HiGain acts as a standby circuit to DS1 circuits whose line codes are not known or may be both AMI and B8ZS). This is because the AUTO mode induces one BPV in the DS1 bit stream when it switches from AMI to B8ZS. The AUTO mode allows both the HLU and the HRU to set its T1 output code to that which is being received at the opposite end's T1 input. This forces the input and the output codes in each direction of transmission to be identical. In the AUTO mode of older HiGain units, the output code was determined by the input code being received at the local T1 input port instead of at the distant end. The HLU reverts to this older code setting technique when it is not connected to an HRU-402 or HRU-411.

Margin Alarm Threshold Option

To set the Margin Alarm Threshold:

- 1 Select **P** from the System Settings Main Menu screen.
- 2 Enter the desired minimum acceptable alarm threshold from the 0 to 15 dB range. This causes a system alarm to occur if either the margin on HDSL Loop 1 (MAL1) or Loop 2 (MAL2) drops below the selected threshold value.



Since the margin can never drop below zero, choosing ${\color{red}0}$ (zero) for the margin threshold turns the margin alarm off.

HAIS Option

The HAIS option provides two selections for the T1 transmit outputs at both the HLU-319 and HRU for HDSL loss of sync conditions.

• 1LP causes the AIS (LOS if ALMP is set to LOS) pattern to be transmitted at both T1 outputs when either of the two HDSL loops experience an out-of-sync (LOSW) condition or when a margin alarm occurs. 1LP causes the 12 channels on the surviving loop to be lost as they are replaced by the AIS/LOS pattern. However, it does notify downstream and upstream equipment of the loss of one HDSL loop or a loop with low margin. This is the preferred setting for initiating an AIS/LOS state with just one conductor open in either of the HDSL pairs. Short loops, below approximately 16 dB of loss at 200 kHz, can remain in sync with one conductor open. Since the loop is still in sync, no LOSW condition occurs. However, the margin on a

one-conductor loop drops from 5 to 10 dB. Therefore, if the Margin alarm is set to 5 dB below the normal margin at turn-up, when one conductor does open, a system alarm occurs and causes the AIS/LOS condition. This alerts the maintenance personnel of the problem.

• **2LP** requires both HDSL loops to be out of sync (LOSW) before the HAIS signal is transmitted. 2LP preserves the integrity of the 12 surviving channels when just one loop is lost.

HDSL Line Voltage Options

The PWRF option has four settings for HDSL line power feed: DIS, LOW, AUTO, and HIGH.

- **DIS** disables any voltage from being applied to the HDSL cable pairs. It is useful to prevent craft personnel from being exposed to the HDSL line voltage when they are working on the cable pairs.
- LOW limits the HDSL simplex voltage to -140 Vdc maximum. This is the standard voltage used in all non-doubler applications and has no effects in these applications. It can be chosen to limit line-powered, single-doubler circuits or locally-powered, two-doubler circuits up to -140 Vdc, if the appropriate HiGain products (HDU-409, HDU-404 or HDU-407 and HRU-402 or HRU-411) are used along with the HLU-319 List 5E. These HiGain units are the only ones that have sufficiently low power consumption to allow their doubler circuits to be line-powered from -140 Vdc. The HRU-411 must have the CPE power option disabled if it is used in a -140 Vdc doubler circuit.
- **AUTO** is the conventional mode in which the HLU automatically maintains the HDSL line voltage at -140 Vdc maximum for non-doubler applications and ±112 Vdc for doubler applications.
- **HIGH** forces the HDSL line voltage to its high ±112 Vdc level for applications. It is needed to allow the HLU to power circuits that are providing power to remote PCS sites.



If the HLU-319 is used with the HRU-411 to power PCS sites, the PWRF option should be set to AUTO. This causes the HLU to automatically detect the need to switch to the HIGH power feed mode when it receives a request from the HRU to do so.

Loopback Mode Screen

The Loopback Menu permits you to issue loopbacks to the HiGain system. Depending upon the number of doublers, there can be up to five loopback screens.

Press **D** from the Maintenance Terminal Main Menu to display the Loopback Menu. Figure 9 shows an example of a Loopback Menu when no doublers are present; Figure 10 shows an example when four doublers are present.

The following options are available:

- Type A to select the Disable Loopbacks option.
- Type **B** to select HLU Network Loop.
- Type **c** to select HRU Network Loop.
- Type **G** to select HLU Customer Loop.
- Type H to select HRU Customer Loop.
- For doubler applications, additional loopback selections appear on the screen.
- Type **E** to exit and return to the previous menu.

Table 9 lists the HLU-319 Loopback field messages and descriptions.

Table 9. Loopback Field Messages and Descriptions

Messages	Full Name	Description
NREM	Network Remote Loopback	Loopback at HRU (remote) towards network.
NLOC	Network Local Loopback	Loopback at HLU (local) towards network.
CLOC	Customer Local Loopback	Loopback at HRU (local) towards CI.
CREM	Customer Remote Loopback	Loopback at HLU (remote) towards CI.
NDU <i>n</i>	Network Doubler <i>n</i> Loopback	Loopback at nth doubler towards network.
CDU <i>n</i>	Customer Doubler n Loopback	Loopback at n^{th} doubler towards CI.

Loopback Menu without a Doubler




Figure 9. Loopback Menu: No Doubler

Loopback Menu for Doubler Applications

```
LOOPBACK MENU
TIME: 00:03:33
DATE: 09/15/99
CIRCUIT ID#:
    A. DISABLE LOOPBACKS
                                 (NLOC)
                                             M. NETWORK LOOP DOUBLER 4
                                                                          (NDU4)
    B. NETWORK LOOP HIJU
    C. NETWORK LOOP HRU
                                 (NREM)
                                             N. CUSTOMER LOOP DOUBLER 4
                                                                          (CDU4)
    D. NETWORK LOOP DOUBLER 1
                                (NDU1)
    F. NETWORK LOOP DOUBLER 2
                                (NDU2)
    G. CUSTOMER LOOP HLU
                                 (CREM)
    H. CUSTOMER LOOP HRU
                                 (CLOC)
    I. CUSTOMER LOOP DOUBLER 1 (CDU1)
    J. CUSTOMER LOOP DOUBLER 2 (CDU2)
    K. NETWORK LOOP DOUBLER 3 (NDU3)
    L. CUSTOMER LOOP DOUBLER 3 (CDU3)
                                    (E)xit
```

Figure 10. Loopback Menu: Four Doublers

Initiating a Loopback

To send one of the available loopbacks, press the appropriate letter in the Loopback Menu. The following prompt appears:

```
PLEASE WAIT.....
```

A series of dots moves from left to right indicating that the command has been issued. When this process completes, the system returns to the Maintenance Terminal Main Menu. The selected loopback four letter designation now appears in the Loopback Mode field in the Maintenance Terminal Main Menu (see Figure 11 on page 29 in which an NLOC loopback is in progress). The loopback continues to cycle in the system depending upon your Loopback Timeout setting.



The Loopback Menu screen is also available at the HRU connected to the HLU-319 List 5E, therefore allowing all HiGain System loopbacks to be initiated from either end of the circuit.

150-319-155-04, Revision 04 Provisioning

```
HI-GAIN HLU-319 MAINTENANCE TERMINAL MAIN MENU (ver V7.2L-5E)
CIRCUIT ID#:

A. VIEW SPAN STATUS
B. SET CLOCK
C. SYSTEM SETTINGS
D. LOOPBACK MODE: NLOC
E. VIEW PERFORMANCE DATA
F. VIEW PERFORMANCE HISTORY
G. VIEW ALARM HISTORY
H. VIEW SYSTEM INVENTORY
I. VIEW TROUBLESHOOTING
```

Figure 11. NLOC Loopback Mode Reported in the Maintenance Terminal Main Menu

Disabling a Loopback

The Disable Loopbacks option (Figure 9 on page 27) allows you to disable (cancel) any of the loopbacks listed in the screen. To disable loopbacks, press **A** in the Loopback Menu. The following prompt appears:

```
PLEASE WAIT.....
```

A series of dots moves from left to right indicating that the command has been issued. When this process completes, the system returns to the Maintenance Terminal Main Menu where the Loopback Mode is identified as None.

View Performance Data Screen

The Performance Data screen shows the Errored (ES) and Unavailable Seconds (UAS) for both HDSL loops and each T1 input at 15-minute intervals over a 4-hour time interval. (The ES and UAS data is separated by a slash mark.) Earlier and later data, in 4-hour time periods on different span screens, can be accessed by pressing P (Previous) or N (Next) respectively.

Errored and Unavailable seconds are defined in Table 10.

Press **E** at the Maintenance Terminal Main Menu to view the Performance Data screen. From each Performance Data screen you can do the following:

- Press P to view the previous 4-hour data screen.
- Press N to view the next 4-hour data screen.
- Press s to view the next available span (for doubler applications).
- Press 1, 2, 3, 4, or 5 to select a specific span (for doubler applications).
- Press E to exit.

Provisioning 150-319-155-04, Revision 04



All Performance Data counters can be set to zero by pressing C (Clear) from the HLU-319 Span Status screen shown in Figure 5 on page 16. The HLU-319 is considered the master module; it clears all performance data screens at both the HLU-319 and the HRU. Counters can not be cleared by accessing the HRU craft port.

Table 10. Errored and Unavailable Seconds Definitions

ES and UAS	Definition
HDSL Errored Second	A second in which at least one HDSL CRC has occurred.
HDSL Unavailable Second	A second in which an HDSL loop experiences loss of sync at least once.
DS1 Errored Second	A second in which at least one BPV, CRC, FRM error, or LOS has occurred.
DS1 Unavailable Second	A second in which at least one T1 LOS condition (175 \pm 75) zeros has occurred.

Performance Data Screen without Doubler

Figure 12 shows a single non-doubler span. This screen shows the Errored and Unavailable Seconds for the HDSL span between the HLU-319 and the HRU.




Figure 12. Performance Data Screen: No Doubler



Dashes that appear on the View Performance Data Screens indicate invalid data.

150-319-155-04, Revision 04 Provisioning

Performance Data Screen for Doubler Applications

Figure 13 is an example of a Performance Data screen that lists performance data for the fifth span (HDU4 to the HRU).

			ERRORED SI	ECONDS/U	NAVAILABLE	SECONDS
	D	S1	HDSI	L-1	HDS	L-2
	HLU	HRU	HLU4	HRU	HDU4	HRU
00:00	,	,	,		/	•
00:15	,	,	,		/	•
00:30	/	/	/	/	/	/
00:45	/	/	/	/	/	/
1:00	/	/	/	/	/	/
1:15	/	/	/	/	/	/
1:30	/	/	/	/	/	/
1:45	/	/	/	/	/	/
02:00	/	/	/	/	/	/
2:15	/	/	/	/	/	/
2:30	/	/	/	/	/	/
2:45	/	/	/	/	/	/
00:00	/	/	/	/	/	/
3:15	/	/	/	/	/	/
3:30	/	/	/	/	/	/
3:45	/	/	/	/	/	/

Figure 13. Performance Data Screen: Four Doublers (Span 5)

View Performance History Screen

The Performance History screen shows the daily occurrences of ES and UAS over a 31-day period in 24-hour increments. Errored Seconds and Unavailable Seconds for both HDSL loops and each of the two DS1 inputs are listed for the current and previous period.

Press **F** at the Maintenance Terminal Main Menu to open the Performance History screen. This screen shows the ES and UAS for the HDSL loop between the HLU-319 and the HRU.

The following options are available:

- Press **s** from the Performance History screen to advance through the history screens for the various spans (for doubler applications).
- From the 31-day Performance History screen press N (Next) for a continued history.
- From the 31-day Performance History screen press P (Previous) for the previous screen.
- Press E to exit from the Performance History screen.



All Performance History counters can be set to zero by pressing © (Clear) from the HLU-319 Span Status screen shown in Figure 5 on page 16. The HLU-319 is considered the master module; it clears all performance data screens at both the HLU-319 and the HRU.

Provisioning 150-319-155-04, Revision 04

Performance History Screen without Doubler

Figure 14 shows a non-doubler application.

```
Time: 00:27:46
                           PERFORMANCE HISTORY - 31 DAY
CIRCUIT ID#:
                       ERRORED SECONDS/UNAVAILABLE SECONDS
                 DS1
                                      HDSL-1
                                                             HDSL-2
                                                         HLU
          HLU
                      HRU
                                  HLU
                                             HRU
                                                                    HRU
01/17
01/18
01/19
01/20
01/21
01/22
01/23
01/24
01/25
01/26
01/27
01/28
                  00002/00002 00004/00014 00006/
                                                     00003/00013 00007/00001
01/29
01/30
01/31
current
                       (E)xit (P)revious
```

Figure 14. 31-Day Performance History Screen: No Doubler



Dashes that appear on the View Performance History Screens indicate invalid data.

150-319-155-04, Revision 04 Provisioning

Performance History Screen for Doubler Applications

The Performance History screen displays information by span when doublers are present. With multiple doublers (up to four), there can be as many as five span screens.

	ERRORED SECONDS/UNAVAILABLE SECONDS							
	DS1 HDSL-1 HDSL-2							
	HLU	HRU	HDU4	HRU	HDU4	HRU		
1/17	/	/		/		/		
01/18	/	/		/		/		
)1/19	/	/		/		/		
1/20	/	/		/		/		
1/21	/	/		/		/		
1/22		/		/				
1/23		/		/				
1/24	/	/		/		/		
1/25	/	/		/		/		
1/26		/		/				
1/27		/		/				
1/28	/	/		/		/		
1/29	00001/	/	00005/00415	/	00035/00492	/		
01/30	/	/	/	/	/	/		
01/31	/	/	/	/	/	/		
current	/	/	/	/	/	/		

Figure 15. 31-Day Performance History Screen: Four Doublers (Span 5)

Provisioning 150-319-155-04, Revision 04

View Alarm History Screen

Press **G** at the Maintenance Terminal Main Menu to open the Alarm History screen. This screen allows you to view alarms that are currently active. In the Alarm History screen (Figure 16 and Figure 17 on page 35) the:

- First and Last columns contain the time and date stamp of the first and last occurrence of each alarm.
- Current column shows the status of each alarm.
- Count column lists the number of times each alarm occurred. (The maximum non-overflowing count is 999.)

From each Alarm History screen you can do the following:

- Press **U** to update the screen.
- Press **S** to view another span (for doubler applications).
- Press **c** to clear all data from the screen.
- Press 1, 2, 3, 4, or 5 to select a specific span (for doubler applications).
- Press E to exit from the Alarm History screen.

Table 11 lists the Alarm History fields and descriptions. These descriptions apply to the Alarm History for doubler applications as well.

Table 11. Alarm History Fields and Descriptions

Field	Description
Туре	Identifies the type of alarm
LOS, DS1-HLU	First and last instance of LOS at the HLU DSX-1 input; Current condition, number of alarms
LOS, DS1-HRU	First and last instance of LOS at the HRU DS1 input; Current condition, number of alarms
AIS, DS1-HLU	First and last instance of AIS at the HLU DSX-1 input; Current condition, number of alarms. (a)
AIS, DS1-HRU	First and last instance of AIS at the HRU DS1 input; Current condition, number of alarms. (a)
BER	First and last instance of a BER; Current condition, number of alarms
Span $n^{(b)}$ LOSW, HDSL1	First and last instance of LOSW on HDSL1; Current condition, number of alarms
Span n LOSW, HDSL2	First and last instance of LOSW on HDSL2; Current condition, number of alarms
Span <i>n</i> Margin L1	First and last instance when margin dropped below the established threshold on Loop 1; Current condition, number of alarms $$
Span <i>n</i> Margin L2	First and last instance when margin dropped below the established threshold on Loop 2; Current condition, number of alarms $$
PWR-SHRT	Power short condition; Current condition, number of alarms
PWR-GND	Power ground condition; Current condition, number of alarms
Last Cleared:	Last time Alarm History cleared; Current condition, number of alarms

⁽a) Requires the HLU-319 to be connected to an HRU-402 or HRU-411.

(b) Where *n* equals span number.

150-319-155-04, Revision 04 Provisioning

Alarm History Screen without a Doubler

	ALARM HISTORY		
TIME: 00:27:54 DATE: 09/15/99 CIRCUIT ID#:			
Type First LOS, DS1-HLU LOS, DS1-HRU AIS, DS1-HRU AIS, DS1-HRU BER SPAN1 LOSW, HDSL1 09/15/99-00 SPAN1 LOSW, HDSL2 09/15/99-00 SPAN1 MARGIN L1 SPAN1 MARGIN L1 PWR-SHRT PWR-GND		Current OK	Count 000 000 000 000 000 001 001 000 000 00
LAST CLEARED: NONE			
(E)3	it (C)lear (U)pdate		

Figure 16. Alarm History Screen: No Doubler

Alarm History Screen for Doubler Applications

The Alarm History screen displays information by span. With no doubler, there is only one span (Figure 16). With multiple doublers (up to four), there can be as many as five span screens. Figure 17 is an example of an Alarm History screen that lists history for the fifth span (Doubler #4 to the HRU).




Figure 17. Alarm History Screen: Four Doublers (Span 5)

Provisioning 150-319-155-04, Revision 04

View System Inventory Screen

The System Inventory screen (Figure 18 on page 37) lists the six possible units that can comprise one HiGain circuit: one HLU, one HRU and up to four doublers. The information in the System Inventory Screen is presented as follows:

- All six possible unit modules are always listed. The doublers are shown as: DB1, DB2, DB3, DB4.
- The model number, list number and software revision number of every unit that is present in the circuit is
 listed in the Product column. Units that are not detected are not considered to be present in the circuit and are
 labeled N/A.
- Each of the unit IDs is limited to 24-character alpha-numeric characters. To change an ID, select its line
 identifying letter. The IDs, like the system settings, are stored in NVRAM and therefore remain when power
 is lost.
- The HLU has no unit ID number since it is usually identified by the Circuit ID number, which appears in every screen.
- All detected modules have the product number listed. When the HLU-319 loses sync with Span 1, the product types are replaced by the N/A label until sync is reestablished and each module can in turn be reidentified. Only the Circuit ID appears in the other HLU-319 List 5E Terminal Maintenance screens.

Press H at the Maintenance Terminal Main Menu to display the System Inventory screen (Figure 18 and Figure 19 on page 37).

From each System Inventory screen (depending on the number of doublers), you can do the following:

- 1 Select the unit for which you want to set the circuit ID by pressing the letter that precedes the unit name.
- 2 Type the circuit ID, then press **ENTER**.
 - You can use up to 24 alphanumeric characters for the circuit ID. If more than 24 characters are entered, a warning beep is emitted and only the first 24 characters are accepted.
- 3 To set the circuit ID for another unit, repeat Step 1 and Step 2.
- 4 Press E to exit the System Inventory screen.
 - The system prompts you to confirm the circuit ID.
- 5 Press C to confirm the circuit ID and exit the System Inventory screen.



Executing the default option from either the front panel or System Settings screen has no effect on the ID values.

150-319-155-04, Revision 04 Provisioning

System Inventory Screen without Doubler

```
SYSTEM INVENTORY
TIME: 00:27:59
                                       A. CIRCUIT ID:
DATE: 09/15/99
        UNIT
                   PRODUCT
                                      UNIT ID
     HLU HLU-319 L5E V7.2 NOT REQUIRED B. HRU HRU-402 L1A V1.3 Remote Unit
     C. DB1 N/A
     D. DB2
              N/A
     F. DB3
              N/A
     G. DB4
              N/A
                                (E)xit
     Enter the item letter to change any ID
```

Figure 18. System Inventory Screen: No Doubler

System Inventory Screen for Doubler Applications

```
SYSTEM INVENTORY
TIME: 18:16:37
DATE: 09/15/99
                                      A. CIRCUIT ID#:
        UNIT
                   PRODUCT
                                         UNIT ID
       HLU HLU-319 L5E V7.2
                                       NOT REQUIRED
     B. HRU
             HRU-402 L1A V1.3
HDU-404 L2 V1.2
                                         Remote Unit
     C. DB1
     D. DB2
              HDU-404 L2 V1.2
HDU-404 L2 V1.2
     F. DB3
     G. DB4 HDU-404 L2 V1.2
                               (E)xit
     Enter the item letter to change any {\tt ID}
```

Figure 19. System Inventory Screen: Four Doublers

Provisioning 150-319-155-04, Revision 04

View Troubleshooting Screen

The Troubleshooting screen graphically analyzes the circuit and identifies any problem areas.

Press I at the Maintenance Terminal Main Menu to access the Troubleshooting screen. The Troubleshooting screen (Figure 20) appears showing the HLU, the HRU and any doublers that are in the circuit (up to four).




Figure 20. Troubleshooting Screen for a Doubler Application

Figure 21 shows an example of a circuit that has identifiable problems. Symbols on the troubleshooting diagram indicate the location of the circuit problems. The legend describes the type of problem.




Figure 21. Troubleshooting Screen Describing Circuit Problem

150-319-155-04, Revision 04 Provisioning

To display the circuit Help diagram (Figure 22), press **H**. The symbol legend used to describe all circuit events and the corresponding troubleshooting tips are located beneath the Help diagram. A troubleshooting symbol on the diagram identifies the location of a problem.



Legend symbols which appear in parentheses are also keyboard commands. Type the symbol in parentheses to access additional troubleshooting data.




Figure 22. Troubleshooting with Help

- Press M to display margin values for the circuit (Figure 23 on page 40).
- Press 1 to display the insertion loss values for the circuit (Figure 24 on page 40).
- Press c to display the HDSL errored seconds screen.
- Press N to display the HDSL unavailable seconds screen.
- Press **R** to display the DS1 errored seconds screen.
- Press o to display the DS1 unavailable seconds screen.

The Troubleshooting screens use the following navigational keyboard commands:

- Press E to return to the Maintenance Terminal Main Menu.
- Press B to return to the main Troubleshooting screen from the Help, Margin Values or Insertion Loss screens.
- Press U to update a screen.
- Press A to automatically update the screen. (Press A again to deactivate auto update.) The Troubleshooting screen indicates whether AutoUpdate is on or off.
- Press L to directly access the Loopback menu (see "Loopback Mode Screen" on page 26).



The first channel reversal (R) of the circuit closest to the line unit is indicated on the Troubleshooting screen. If another channel reversal exists, it will be identified as soon as the preceding channel reversal is corrected.

Provisioning 150-319-155-04, Revision 04

Press M to display margin values for the circuit (Figure 23).




Figure 23. Troubleshooting with Margin Values

Press I to display the insertion loss values for the circuit (Figure 24).




Figure 24. Troubleshooting with Insertion Loss Values

150-319-155-04, Revision 04 Provisioning

Press C to display the HDSL errored seconds, or press R to display DS1 errored seconds for the circuit (Figure 25).




Figure 25. Troubleshooting with 24-Hour Errored Seconds (ES)

Press N to display HDSL unavailable seconds, or press O to display DS1 unavailable seconds for the circuit (Figure 26).




Figure 26. Troubleshooting with 24-Hour Unavailable Seconds (UAS)

Troubleshooting 150-319-155-04, Revision 04

TROUBLESHOOTING

This section provides information about system alarms and loopback testing. In addition to these troubleshooting aids, the Maintenance Terminal provisioning interface includes troubleshooting screens that provide a basic graphical analysis of system problems (see "View Troubleshooting Screen" on page 38).

SYSTEM ALARMS

Table 12 lists possible HLU-319 List 5E alarm states and the corresponding front-panel messages. More than one alarm condition can exist at any given time, but only one message can be displayed. For multiple alarms, only the highest priority alarm displays.

Table 12. HDSL System Alarms

Front-panel Message	Alarm State	Description	To Inhibit:
ALRM LOSW	Loss of Sync Word ^(a)	One of the HDSL loops has lost synchronization.	Cannot be inhibited.
ALRM LLOS	Local Loss of Signal	Loss of the DSX-1 input signal.	Cannot be inhibited.
ALRM RLOS	Remote Loss of Signal	Loss of the HRU DS1 input signal.	Disable the RDA (Remote DS1 Alarm) option. This prevents an LOS condition at the DS1 input to a HRU from closing the alarm contacts (pins 20 and 21 on the card-edge connector). The front-panel Status LED still flashes red and the ALRM RLOS message displays to alert you of the LOS state. LOS is sent towards the network from the HLU. This option prevents the common occurrences of a CPE LOS condition from generating recurring alarms and AIS payloads.
ALRM R(L)AIS (b)	Remote (or Local) Alarm Indicating Signal	Indicates an AIS pattern of all ones is being transmitted (XMT) from the remote (or local) T1 output port.	Set LBPK option to ENA or DIS.
ALRM MAL1 or ALRM MAL2	Margin Alarm Loop1 or Margin Alarm Loop2	The margin on HDSL Loop 1 or Loop 2 has dropped below the minimum threshold value set by the terminal MARGIN ALARM THRES.	Set the Margin Alarm Threshold option to 0 (zero).
ALRM BER	Bit Error Rate exceeded	The combined T1 and HDSL BER has exceeded you set threshold limits of 10^{-6} or 10^{-7} .	Select NONE for the BER system option.
NONE	No alarm	No current alarm condition.	Cannot be inhibited.

⁽a) When both HDSL loops lose sync word (LOSW), a system alarm condition exists. However, since the HLU-319 enters a self test cycling mode, the front-panel LED lights yellow instead of red and the SELF TEST message displays instead of the ALRM message.

⁽b) This message is reported in the Span Status screens, but not on the front-panel display. HLU must be connected to the HRU-402 or HRU-411 and LPBK option must be set to ENFT.

150-319-155-04, Revision 04 Troubleshooting

Alarm Option for DLC Feed

To improve HiGain compatibility with the switch-to-protect features used in DLC feeder applications, the HLU-319 has an Alarm Pattern Option (ALMP) that allows you to select either an AIS or LOS T1 output payload for the following alarms:

- LOSW on any loop
- T1 LOS
- Margin alarm if HAIS = 1 Loop

Retiring System Alarms

To retire a system alarm, press the SEL button and execute an Alarm Cut Off (ACO). An ACO turns the alarm off and replaces the ALRM message with an ACO message. The second part of the ALRM message, which defines the cause of the alarm, remains. Both parts of the message remain until the alarm condition clears or another higher priority alarm occurs.

Self Test

The Self Test mode that occurs when both HDSL loops are not in sync has been enhanced to include the input DS1 transceiver chip. The Self Test procedure can cause the all ones pattern, that is normally transmitted from the HLU-319 during these out-of-sync intervals, to exhibit occasional BPVs.

Troubleshooting 150-319-155-04, Revision 04

LOOPBACK OPERATION

HiGain has a family of loopback options for analyzing circuit functionality. The loopback signal is transmitted and returned to the sending device for comparison. This allows you to verify the integrity of the HDSL channels to the HLU, the HLU DSX-1 interface and the DS1 channels to the customer. Loopback options include:

- Generic Loopback (GNLB) options, including the SmartJack (SMJK) option (Table 13 on page 45)
- Special Loopback (SPLB) options (see "Special Loopback Commands" on page 46 and the following tables
 - Addressable Repeater Loopback commands: A1LB, A2LB, A5LB (Table 14 on page 50)
 - Addressable Repeater Loopback commands: A3LB, A4LB (Table 15 on page 53)

Loopback commands can be initiated by:

- selecting the loopback type using the MODE and SEL buttons on the HLU (or the Manual Loopback button on the HRU)
- selecting the loopback type from the Maintenance Terminal Main Menu when connected to the craft port of the HLU or HRU
- entering the loopback code into the test equipment connected to the HLU or HRU

Generic Loopback Commands

The HiGain Generic Loopback (GNLB) commands allow you to use inband codes to loop up either NLOC (4-in-7) or NREM (3-in-7) towards the network. In addition, these inband codes loop up CREM (6-in-7) or CLOC (5-in-7) towards the customer. Either loop-up condition can be terminated (looped down) with the 3-in-5 SMJK loop-down code. All inband codes must be present for 5 seconds before the HiGain system responds. HiGain also supports NDUn doubler loopbacks to the network and CDUn doubler loopbacks towards the customer.

Figure 27 summarizes the available loopbacks in the system, and Table 13 on page 45 summarizes the HiGain generic loopback commands. See "GNLB Test Procedures" on page 48 for the test procedures that apply when using the GNLB mode.




Figure 27. Loopback Summary

150-319-155-04, Revision 04 Troubleshooting

Table 13. Summary of HiGain Loopback Codes

			Meth	Method of Transmission			
Loopback	Code	Description	Test Set	Craft Port	MODE/SEL		
NLOC	1111000 4-in-7	Network Local. Invokes HLU loopback toward the network.	Х	Х	Х		
NDU1	110000 2-in-6	Network Doubler 1. Invokes HDU1 loopback toward the network.	Х	Х	Х		
NDU2	111000 3-in-6	Network Doubler 2. Invokes HDU2 loopback toward the network.	Х	Х	Х		
NDU3	1010001	Network Doubler 3. Invokes HDU3 loopback toward the network.	Х	Х	Х		
NDU4	1010010	Network Doubler 4. Invokes HDU4 loopback toward the network.	Х	Х	Х		
NREM	1110000 3-in-7	Network Remote. Invokes HRU loopback towards the network.	Х	Х	Х		
CLOC	1111100 5-in-7	Customer Local. Invokes HRU loopback towards the customer.	Х	Х	Х		
CDU1	111100 4-in-6	Customer Doubler 1. Invokes HDU1 loopback towards the customer.	Х	Х	Х		
CDU2	111110 5-in-6	Customer Doubler 2. Invokes HDU2 loopback towards the customer.	Х	Х	Х		
CDU3	1011001	Customer Doubler 3. Invokes HDU3 loopback towards the customer.	Х	Х	Х		
CDU4	1011010	Customer Doubler 4. Invokes HDU4 loopback towards the customer.	Х	Х	Х		
CREM	1111110 6-in-7	Customer Remote. Invokes HLU loopback towards the customer.	X	Χ	Χ		
SMJK LpUp (PL)	11000 2-in-5	SmartJack Loopup or Network Interface Device (NID) payload (PL) code. Invokes HRU loopback towards network.	X				
SMJK LpUp (ESF-DL)	1111-1111- 0100-1000	SmartJack Loopup or NID (ESF-DL) code. Invokes HRU loopback towards network.	Х				
SMJK LpDn (PL)	11100 3-in-5	SmartJack Loopdown or NID payload (PL) code. Removes SMJK, NLOC, NREM, CREM, CLOC, CDU <i>n</i> , and NDU <i>n</i> .	Х				
SMJK LpDn (ESF-DL)	1111-1111- 0010-0100	SmartJack Loopdown or NID (ESF-DL) code. Removes SMJK, NLOC, NREM, CREM, CLOC, CDU <i>n</i> , and NDU <i>n</i> .	Х				



HiGain systems feature the SmartJack option, which can emulate an NID for the purpose of loopback testing of the HiGain circuit. SMJK and NREM loopbacks perform the same functions but their initiation differs. SMJK indicates that the loopback was initiated by the 2-in-5 inband command. NREM, on the other hand, is initiated by the 3-in-7 inband command or by a command issued from the maintenance terminal or the MODE and SEL buttons.

Use the inband commands to enable or disable the SMJK loopback options. The HLU system setting is normally enabled to recognize all inband SmartJack loopback commands.

Troubleshooting 150-319-155-04, Revision 04

Special Loopback Commands

In addition to the GNLB loopback command mode, a HiGain system can be configured for one of five special loopback command modes. These are selected from the maintenance terminal System Settings screen (see Table 8 on page 21) or by using the MODE and SEL buttons (see Figure 28 on page 49). Once a loopback mode is activated, other loopback commands can be sent by a test set connected to the craft port of the HLU or HRU (see Table 14 on page 50 and Table 15 on page 53 for list of SPLB commands).

A1LB through A5LB are five special, addressable, repeater loopback modes which are supported by the HLU-319 List 5E. These loopback modes provide the HiGain system with sophisticated maintenance and troubleshooting tools. A1LB, A2LB, and A5LB are patterned after the Teltrend addressable T1 repeater loopbacks. A3LB and A4LB are patterned after the Wescom addressable T1 repeater loopbacks. All five SPLBs have been enhanced to handle the specific requirements of the following HiGain customers:

- A1LB (Teltrend) = Southwestern Bell
- A2LB (Teltrend) = Southwestern Bell
- A3LB (Wescom) = New England Telephone
- A4LB (Wescom Mod 1) = New York Telephone
- A5LB (Teltrend Mod 1) = Southern New England Telephone (SNET), Southwestern Bell, Pacific Bell

The A1LB loopback selection complies with that proposed for HDSL systems in the T1E1.4/92 recommendation with the following additions:

- query loopback
- IOR (Intelligent Office Repeater) power-down
- · four loopback time-out choices
- initiation from either end
- repeating bit error signatures
- alternate query loopback

These additions make A1LB identical to A2LB. A1LB is given a separate identity to allow future T1/E1 enhancements to be added without affecting A2LB.

A5LB differs from A2LB in that A5LB does not block the arming code from exiting the HLU-319 into the network. A2LB can be configured to do one of the following:

- block the arming code (after 2 seconds) from exiting the HLU into the network, and replace it with the AIS
 code.
- unblock the AIS code by executing the Far-End Activate code. (Since A5LB never blocks the arming code from exiting the HLU, the Far-End Activate code is not available in A5LB.)

A3LB differs from A4LB in that A3LB supports the additional (1-in-6) SMJK loopback command.



A HiGain system may take longer than normal to respond to inband loopback commands when its framing mode is set to UNFR and the inband commands are set in either SF or ESF mode. The frame bits override the command bits and cause errors in the command sequence. These errors cause the HiGain system to reject some sequences.

150-319-155-04, Revision 04 Troubleshooting

Initiating a Manual Loopback Session

A manual loopback session allows you to select any one of the HiGain GNLB loopbacks listed in Table 13 on page 45 with the exception of SmartJack loopbacks, which can only be issued by inband commands.

Setting the Loopback Time-out Option

Before initiating a loopback session, verify that the Loopback Time-out parameter is set to the desired setting.

- 1 Use the MODE and SEL buttons as described in "Setting Options through MODE and SEL" on page 11. (The Loopback Time-out parameter is also user-selectable from the System Settings screen when using a maintenance terminal.)
- **2** Enter the desired setting:
 - NONE (no time-out)
 - 20 minutes
 - 60 minutes (default setting)
 - 120 minutes

Initiating a Manual Loopback Session



With the exception of SmartJack, any of the HiGain loopbacks can be executed using the MODE and SEL buttons.

When executing a manual loopback session using the MODE and SEL buttons:

- The next loopback option can be presented by pressing the MODE button, however, the
 previously activated loopback remains active until the SEL button is pressed, which
 activates the new loopback.
- If neither button is pressed for a period of 30 seconds and no loopback is in effect, the manual loopback session terminates and the display returns to normal mode.
- If any loopback is in effect, the 30-second time-out is inhibited. The active loopback and the
 manual loopback session continue until the loopback times out in accordance with the LBTO
 setting.
- Only the SMJK loopback can exist with other network loopbacks at any given time.
- If there is an active loopback, pressing the MODE and SEL buttons for 3 or more seconds terminates any active loopback, ends the manual loopback session and returns the display to normal mode.

To initiate a manual loopback session:

Press both the MODE and SEL buttons on the front panel for at least 3 seconds. The following message appears on the front-panel display:

MAN LPBK NLO?

- 2 Press SEL to activate NLOC. The display changes to MAN LPBK NLOC.
- 3 Press MODE to advance to the next available loopback (ND1? ND2? ND3? ND4? NRE? CRE? CD1? CD2? CD3? CD4? CLO?).
- 4 Press SEL to activate the selected loopback. The previous loopback is terminated.

Once a loopback is selected and activated, the loopback stays active until it times out (based on the LBTO setting). When a loopback times out, the display then returns to the normal display mode.

Troubleshooting 150-319-155-04, Revision 04

You can terminate loopbacks manually and exit the MAN LPBK mode by simultaneously pressing the MODE and SEL buttons for 3 or more seconds. If no loopback is active, the MAN LPBK mode automatically terminates after 30 seconds.

All loopbacks can be initiated by inband commands in the T1 payload or by a command from the HiGain system (front-panel buttons or maintenance screen selections). Therefore, when a loopback is active, the method by which it was activated is indicated in the Loopback and Status screens by the annotation HG (HiGain) or PL (Payload) adjacent to the identified loopback. For example, NREM (HG) indicates that the loopback was initiated by the HiGain system.



SMJK loopback commands are only activated by inband commands.

LOOPBACK TEST PROCEDURES

The following sections provide step-by-step test procedures for verifying the integrity of the HDSL channels at every module location as well as the DS1 channels to the customer and the local DSX-1 interface.

General Troubleshooting Tips

If trouble is encountered on the DSX-1 interface of the HLU-319, verify that the:

- HLU is making a positive connection with its mounting assembly (shelf) connector.
- HLU internal equalizer is set to the correct distance range per Table 8 on page 21. All equalizers should be set to the distance from the DSX-1 to the shelf.

The transmit and receive T1 DSX-1 ports have splitting access jacks and miniature, 210-series, bridging jacks as shown in Figure 1 on page 4. Connecting one cable between the two bridging jacks and another between the two SPAN jacks splits the XMT and RCV and creates metallic loopbacks towards both the DSX-1 and the HLU-319. If separate plugs are inserted into both SPAN jacks with the other end disconnected, the BRG jacks can be used to send and receive test patterns towards the DSX-1.


GNLB Test Procedures

Figure 28 on page 49 is a graphical representation of the various generic loopback configurations with the associated GNLB commands shown. Also, refer to Table 13 on page 45 for a description of these commands.

To perform the GNLB loopback test procedure:

- Have the CO tester send the NREM (3-in-7) inband loopup code for 5 seconds. You should be able to observe the NREM message on the front-panel display. (The Status LED on the front panel should be green, and the loopback mode should also be identified on the Span Status screen.)
- 2 Have the CO tester transmit a T1 test signal towards the HLU-319 and verify that the returned (looped) signal to the test set is error-free.
- 3 If step 2 fails, have the CO tester transmit the (3-in-5) inband loopdown code.
- 4 Have the CO tester send the NLOC (4-in-7) inband loopup for 5 seconds. You should be able to observe the NLOC message on the front-panel display. (The Status LED on the front panel should be yellow, and the loopback mode should also be identified on the Span Status screen.)
- 5 Repeat Step 2. If the test passes, the problem is in the downstream direction. If it fails, the problem is in the upstream direction.

150-319-155-04, Revision 04 Troubleshooting



^{*} Set the SAIS option to ENA to send AIS (indicated by an all ones pattern) to the CI during SmartJack loopback, NREM, and TLOS. Use the 3-in-5 code to loop down.

Figure 28. Loopback Configurations

Troubleshooting 150-319-155-04, Revision 04

A1LB, A2LB, and A5LB Test Procedures

Using the codes listed in Table 14, a network tester can activate NLOC or NREM loopbacks (or SMJK, if enabled). A tester at the customer premises can activate CLOC or CREM loopbacks. All loopbacks shown in Table 14 can also be initiated from the HLU-319 front-panel MODE and SEL buttons (see "Setting Options through MODE and SEL" on page 11). Information specific to HiGain doublers is shown in bold type.

Table 14. Addressable Repeater Loopback Commands (A1LB, A2LB, A5LB)

Name	Description	Binary Code ^(a) (Hexadecimal Equivalent)
ARMING or Network Interface (NI) LPBK (inband)	Arming code	11000-11000
ARMING or NI LPBK (ESF Data Link)	Arming code	1111-1111-0100-1000 (FF48)
IR LPDN or DISARM (inband)	Disarming code	11100-11100
IR LPDN or DISARM (ESF Data Link)	Disarming code	1111-1111-0010-0100 (FF24)
IOR LPBK (NLOC and CREM 230-232 bit errors and 229-231 bit errors) (b)	HLU loopup	1101-0011-1101-0011 (D3D3)
ILR-1 LPBK (NDU1 and CDU1 10 bit errors) ^(b)	HDU1 loopup	1100-0111-0100-0001 (C741)
ILR-20 LPBK (NDU2 and CDU2 200 bit errors)	HDU2 loopup	1100-0111-0101-0100 (C754)
ILR-3 LPBK (NDU3 and CDU3 30 bit errors)	HDU3 loopup	1100-0111-0100-0011 (C743)
ILR-4 LPBK (NDU4 and CDU4 40 bit errors)	HDU4 loopup	1100-0111-0100-0100 (C744)
ILR-2 LPBK (NREM and CLOC 20 bit errors)	HRU loopup	1100-0111-0100-0010 (C742)
IR LPDN	Loopdown (HLU, HDU, or HRU)	1001-0011-1001-0011 (9393)
IR QUERY LPBK	Query loopback	1101-0101-1101-0101 (D5D5)
IR ALTERNATE QUERY LPBK	Alternate query loopback	1101-0101-1110-1010 (D5EA)
TIME-OUT OVERRIDE	Loopback time-out override	1101-0101-1101-0110 (D5D6)
FAR END NI ACTIVATE (c)	Unblock AIS	1100-0101-0101-0100 (C554)
IOR POWER DOWN (HLU) (d)	Removes HDSL line power	0110-0111-0110-0111 (6767)

⁽a) The left most bit arrives first in all sequences. The detection algorithm functions reliably with a random 10⁻³ Bit Error Ratio (BER) on the facility. The entire arming and loopback sequence can also be initiated at the remote HRU location.

⁽b) The HRU identifies CREM (and the HLU identifies NLOC) with 231 bit errors, including the frame bits. When framed data is being sent in the AUTO framing mode, the number of the 231 bit errors detected by the test set varies from 229 to 231, depending on whether or not the test set counts frame errors as bit errors, and on the number of frame bits contained in the block of 231 error bits. The HRU and HLU generate this bit pattern in a series of discontinuous bursts containing 20-bit errors each, including frame bits. Those test sets that do not count frame error bits as data bit errors will indicate fewer bits than the HRU and HLU transmit for a CI and NI loopback.

⁽c) Sending the Far-End NI Activate code is not required in A5LB because it is always activated.

⁽d) The IOR Power Down code must remain present for the duration of the power down mode. When this code is removed, the HiGain system returns to its normal unlooped and unarmed state.

150-319-155-04, Revision 04 Troubleshooting

To perform the A1LB, A2LB, and the A5LB test procedures:

- 1 Send the inband Arming and NI LPBK code 11000 to the HLU-319 for at least 5 seconds.
- 2 Monitor the output of the HLU-319 for the return of the pattern. Return of the pattern indicates one of the following:
 - the HRU has looped up (if the SMJK Loopback option is Enabled)
 - an external NI has looped up (if the SMJK Loopback option is Disabled), and the HLU and HRU have been armed
- 3 Verify, if possible, that the HRU Loopback LED is either flashing yellow at 4-second intervals (indicating that the system is armed), or is a steady yellow (indicating that it is both armed and in SMJK loopback). The HLU Status LED also flashes yellow when the system is armed.
- 4 Once armed, the HLU-319 can be looped back by sending Intelligent Office Repeater (IOR) LPBK activation code 1101-0011-1101-0011 (D3D3) for at least 5 seconds. You should observe the following activation response pattern in the order presented:
 - a 2 seconds of AIS (identified by an all ones pattern)
 - **b** 2 seconds of returning data pattern
 - c 231 logic errors (including the frame bit) occurring in the returned pattern comprising:
 - 10 errors, if ILR-1 (Doubler 1) was sent
 - 200 errors, if ILR-20 (Doubler 2) was sent
 - 30 errors, if ILR-3 (Doubler 3) was sent
 - 40 errors, if ILR-4 (Doubler 4) was sent
 - 20 errors, if ILR-2 (HRU) was sent
 - **d** normal looped data

This error pattern repeats every 20 seconds as long as the IOR loopback pattern is being sent. This also applies to ILR, Time-out Override, and Query commands.



Some Intelligent Repeater (IR) test sets do not count frame errors as bit errors when the test pattern is framed and the HLU-319 is set to the Auto framing mode. To improve compatibility with those test sets, the HLU-319 generates 201 (NDU2 and CDU2) and 232 (NLOC and CREM) ID bit errors. As a result, the HLU-319 may indicate one more or one less bit error, depending on the test set type and the number of frame bits contained in the block of errored bits. To avoid this uncertainty, PairGain recommends sending unframed IR commands.

The HLU is now in logic loopback if the IOR NLOC loopback command was sent. The Time-out Override command or a Loopdown command can override the selection made for the loopback time-out (see "Setting the Loopback Time-out Option" on page 47). If the Time-out Override code 1101-0101-1101-0110 (D5D6) is received after activating a loopback, then the automatic timed expiration of the loopback is inhibited. If this Time-out Override is sent, then the only way to loop the HLU-319 down is to do one of the following:

- issue the IR LPDN (loopdown) code 1001-0011-1001-0011 (9393)
- issue the NI LPDN and Disarm inband code 11100 or the ESF-DL code (FF24).



The Time-out Override function is only valid for the current active loopback. The automatic time-out timer is restored during subsequent loopback sessions.

Troubleshooting 150-319-155-04, Revision 04

- 5 Once the test is complete, do one of the following:
 - If the system is to loopdown but remain Armed, send the IR LPDN code (universal loopdown).
 - If all the equipment is to be looped down, disarmed and returned to normal operation, send the disarm inband code 11100 or the ESF-DL code (FF24).



The Armed mode has an automatic time-out of 120 minutes but this timer is reset to 120 for any of the following events:

- Loopback terminates (manually or time-out),
- Query
- · Alternate query
- · Far end activate
- Another ARM command.

This timer is inhibited while any of the valid command codes are being sent. Once the codes are removed, the timer restarts at 120.

150-319-155-04, Revision 04 Troubleshooting

A3LB and A4LB Test Procedures

The HLU-319 can be looped back by sending the Addressable Office Repeater (AOR) LPBK activation code 1111-1111-0001-1110 (FF1E) for at least 5 seconds. This causes the HLU-319 to enter the NLOC state. The Loopback Time-out setting (see "Setting the Loopback Time-out Option" on page 47) determines the duration of this loopback unless it is overridden by the reception of a second identical 16-bit loop-up command before the timer expires. When this time-out override state exists, the only way to loop the HLU-319 down is to issue one of the three loopdown commands listed in Table 15. The automatic time-out mode is restored during subsequent loopback sessions.

Table 15 summarizes the codes required to execute Addressable 3 and 4 (A3LB and A4LB) repeater loopback commands. All code sequences must be present for at least 5 seconds. Information specific to HiGain doublers is shown in bold.

	Table 15.	Addressable	Repeater	Loopback	Commands	(A3LB and A4LB))
--	-----------	-------------	----------	----------	----------	-----------------	---

Name	Description	Binary Code (a) (Hexadecimal Equivalent)
NLOC	HLU-319 line unit from NI	1111-1111-0001-1110 (FF1E)
CREM	HLU-319 line unit from CI	0011-1111-0001-1110 (3F1E)
NDU1	HDU doubler 1 from NI	1111-1111-0000-0100 (FF04)
CDU1	HDU doubler 1 from Cl	0011-1111-0000-0100 (3F04)
NDU2	HDU doubler 2 from NI	1111-1111-0000-0110 (FF06)
CDU2	HDU doubler 2 from CI	0011-1111-0000-0110 (3F06)
NDU3	HDU doubler 3 from NI	1111-1111-0000-1000 (FF08)
CDU3	HDU doubler 3 from CI	0011-1111-0000-1000 (3F08)
NDU4	HDU doubler 4 from NI	1111-1111-0000-1010 (FF0A)
CDU4	HDU doubler 4 from CI	0011-1111-0000-1010 (3F0A)
NREM	HRU loopup from NI	1111-1111-0000-0010 (FF02)
CLOC	HRU loopup from CI	0011-1111-0000-0010 (3F02)
SMJK	HRU loopup from NI	11000-11000-11000
SMJK	HRU loopup from NI (b)	100000 100000 100000
SMJK	HRU loopup from NI (ESF-DL)	1111-1111-0100-1000 (FF48)
Loopdown	HLU and HRU loopdown from NI OR CI	11100-11100-11100
Loopdown	HLU and HRU loopdown from NI OR CI	100-100-100
Loopdown	HLU and HRU loopdown from NI OR CI (ESF-DL)	1111-1111-0010-0100 (FF24)

⁽a) The left-most bit arrives first in all sequences. The detection algorithm functions reliably with a random 10⁻³ Bit Error Ratio (BER) on the facility. The entire arming and loopback sequence can also be initiated at the remote HRU location.

⁽b) Not supported by A4LB.

Appendix A - Specifications 150-319-155-04, Revision 04

APPENDIX A - SPECIFICATIONS

This appendix provides general specifications, pinout diagrams for the craft port and card-edge connector, HDSL insertion loss guidelines, and power consumption and dissipation tables.

HDSL Line Code 784 kbps 2B1Q

HDSL Output $+13.5 \text{ dBm } \pm 0.5 \text{ dB at } 135 \Omega$

HDSL Line Impedance 135 Ω

Maximum Provisioning Loss35 dB at 196 kHz, 135 Ω Line Clock rateInternal "Stratum 4" clock

HDSL Start-up Time 30 sec. (typical), 60 sec. (maximum) per span

One-way DS1 Delay <200 µs per span without doublers. Doubler delay <80 µs

DSX-1 Line Impedance 100Ω

DSX-1 Pulse Output 6 V pk-pk, pre-equalized for 0-655 feet of ABAM cable

DSX-1 Input Level+1.5 to -7.5 dBDSXDS1 Line Rate1.544 Mbps ±200 bpsDS1 Line FormatAMI, B8ZS or ZBTSIDS1 Frame FormatESF, SF or UNFR

Maximum Heat Dissipation See "Power Consumption" on page 55

Fusing Internal; connected to Fuse Alarm output on pin 10

HDSL Span Voltage $-140 \text{ or } \pm 112 \text{ Vdc}$

Electrical Protection Secondary surge and power cross protection on HDSL ports. Requires

external primary protection

Operating Temperature $-40 \,^{\circ}\text{F} \, (-40 \,^{\circ}\text{C}) \text{ to } +149 \,^{\circ}\text{F} \, (+65 \,^{\circ}\text{C})$

Operating Humidity 5% to 95% (non-condensing)

Mounting STS high density shelf

Dimensions

Height: 4.750 in. (12.10 cm)
Width: 0.625 in. (1.59 cm)
Depth: 10 in. (25.4 cm)
Weight: 0.8 oz. (.23 kg)

Wander (Looped) 0.3 UI maximum (1 UI = 648 ns)

WB Jitter (Looped) 0.2 UI maximum
NB Jitter (Looped) 0.1 UI maximum

150-319-155-04, Revision 04 Appendix A - Specifications

HDSL Insertion Loss Guidelines

Each loop has no more than 35 dB of loss at 196 kHz, with driving and terminating impedances of 135 Ω . Table 16 provides a "loss" guide for the various cable gauges at 196 kHz and 135 Ω . The table applies to the HDSL cable pairs between the HLU, HRU, and HDU modules. In the absence of specific insertion loss measurement data, add 3 dB for each bridged tap and 1 dB for each cable gauge change.

Table 16. HDSL Loss Over Cables

Cable Gauge	Loop Loss ^(a) (dB per kft)	Loop Resistance (Ω per kft)
26 AWG / 0.4 mm	3.88	83
24 AWG /0.51 mm	2.84	52
22 AWG /0.61 mm	2.18	32
19 AWG /0.91 mm	1.54	16
(a) At 196 kHz, 68°F (20°C)		



A Windows-based program, Cable Calculator, may be downloaded from the Customer site portion of the PairGain web site at *www.pairgain.com*. If you don't have a customer password, contact your sales representative.

POWER CONSUMPTION

Power consumption and heat dissipation depends upon the type of remote and doubler units in the system and the CPE power setting.

Power Consumption without Doublers

The three most important power parameters of an HLU are its maximum power consumption, its maximum power dissipation and its maximum current drain.

Table 17 describes line-powered circuits on 9 kft, 26 AWG loops without a doubler.

Table 17. HLU-319 Power Parameters—No Doubler

HRU Model No.	HRU CPE Power	42.5 Vdc Power Consumption (Watts)		Heat Dissi	pation (Watts)	42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-412 List 1, 2, 3, 4	ON	12.0	13.2	5.1	5.6	284	312
HRU-412 List 1, 2, 3, 4	OFF	11.0	12.1	5.0	5.5	260	286
HRU-412 List 6, 7, 8	ON	12.6	13.9	5.2	5.7	297	327
HRU-412 List 6, 7, 8	OFF	9.7	10.7	4.5	4.9	228	251
HRU-402	N/A	7.7	8.5	4.5	4.9	182	200
HRU-411 (a)	ON	21.0	23.1	6.3	6.9	495	544
HRU-411	OFF	8.2	9.0	5.2	5.7	193	212

(a) HLU-319 PWRF option set to HIGH.

Appendix A - Specifications 150-319-155-04, Revision 04

Power Consumption with Doublers

Table 18 through Table 24 list the power consumed and dissipated by the HLU-319 when it is used with any of the four basic doubler types in the HiGain family. The maximum current drawn by the CO supply is also listed.

Table 18 through Table 20 shows power parameters for single doubler, line-powered circuits on 9 kft, 26 AWG loops.

 Table 18.
 HLU-319 Power Parameters—Single Doubler (HDU-451 List 1 or 2)

HRU Model No.	HRU CPE Power	42.5 Vdc Power Consumption (Watts)		Heat Dissi	pation (Watts)	42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-412 List 1, 2, 3, 4	ON	27.5	30.3	7.6	8.4	646	711
HRU-412 List 1, 2, 3, 4	OFF	25.9	28.5	7.2	7.9	610	671
HRU-412 List 6, 7, 8	ON	27.7	30.5	7.6	8.4	651	716
HRU-412 List 6, 7, 8	OFF	24.3	26.7	7.1	7.8	571	628
HRU-402	N/A (OFF)	21	23.1	6.3	6.9	494	543
HRU-411	OFF	20	22.0	6.2	6.8	471	518

Table 19. HLU-319 Power Parameters—Single Doubler (HDU-439 or HDU-437 Lists 1 and 1B)

HRU Model No.	HRU CPE Power	42.5 Vdc Power Consumption (Watts) Heat Dis		Heat Dissi	pation (Watts)	42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-412 List 1, 2, 3, 4	ON	22.3	24.5	7.9	8.6	525	578
HRU-412 List 1, 2, 3, 4	OFF	21.4	23.5	7.8	8.5	502	552
HRU-412 List 6, 7, 8	ON	22.3	24.5	8.0	8.8	524	576
HRU-412 List 6, 7, 8	OFF	19.2	21.1	7.3	8.1	452	497
HRU-402	N/A (OFF)	16.0	17.6	6.7	7.4	376	414
HRU-411	OFF	15.6	17.2	6.7	7.4	367	404

 Table 20.
 HLU-319 Power Parameters—Single Doubler (HDU-409 List 2, HDU-407 List 2, and HDU-404 List 2)

HRU Model No.	HRU CPE Power	42.5 Vdc P Consumpti	ower on (Watts)	Heat Dissi	pation (Watts)	42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-412 List 1, 2, 3, 4	ON	18.8	20.7	7.0	7.7	442	486
HRU-412 List 1, 2, 3, 4	OFF	18.0	19.8	7.1	7.8	424	466
HRU-412 List 6, 7, 8	ON	18.4	20.2	6.9	7.6	433	476
HRU-412 List 6, 7, 8	OFF	15.7	17.3	6.8	7.4	370	407
HRU-402	N/A (OFF)	12.5	13.8	5.9	6.5	294	323
HRU-411	OFF	12.0	13.2	5.8	6.4	283	311

150-319-155-04, Revision 04 Appendix A - Specifications

Table 21 through Table 23 show power parameters for two doubler, line-powered circuits on 9 kft, 26 AWG loops.

Table 21. Hi	LU-319 Power Paramet	ers—Two Doublers ((HDU-451 List 3. 4	3B or 4B

HRU Model No.	HRU CPE Power	42.5 Vdc Power Consumption (Watts)		Heat Dissipation (Watts)		42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-402	N/A (OFF)	28.3	31.1	8.3	9.1	665	732
HRU-411	OFF	28.1	30.9	8.2	9.0	661	727

 Table 22.
 HLU-319 Power Parameters—Two Doublers (HDU-439 or HDU-437 List 1 and 1B)

HRU Model No.	HRU CPE Power	42.5 Vdc Power Consumption (Watts)		Heat Dissipation (Watts)		42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-412 List 1, 2, 3, 4	OFF	30.3	33.3	8.0	8.8	713	784
HRU-412 List 6, 7, 8	OFF	28.1	30.9	7.7	8.5	660	726
HRU-402	N/A (OFF)	24.8	27.3	7.2	7.9	584	642
HRU-411	OFF	27.7	30.5	7.5	8.3	652	717

 Table 23.
 HLU-319 Power Parameters—Two Doublers (HDU-409 List 2, HDU-407 List 2, and HDU-404 List 2)

HRU Model No.	HRU CPE Power	42.5 Vdc P Consumpti	ower on (Watts)	Heat Dissi	pation (Watts)	42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-412 List 1, 2, 3,4	ON	24.4	26.8	7.2	7.9	575	633
HRU-412 List 1, 2, 3,4	OFF	22.1	24.3	6.8	7.5	520	572
HRU-412 List 6, 7, 8	ON	25.9	28.5	7.4	8.1	609	670
HRU-412 List 6, 7, 8	OFF	20.2	22.2	6.4	7.0	476	524
HRU-402	N/A (OFF)	17.4	19.1	7.1	7.8	410	451
HRU-411	OFF	16.5	18.2	6.0	6.6	389	428

Table 24 shows power parameters for three doubler, line-powered circuits or four doubler, locally-powered circuits on 9 kft, 26 AWG loops.

Table 24. HLU-319 Power Parameters—Three and Four Doublers (HDU-409 List 2, HDU-407 List 2, and HDU-404 List 2)

HRU Model No.	HRU CPE Power	42.5 Vdc Power Consumption (Watts)		Heat Dissipation (Watts)		42.5 Vdc Current (mA)	
		Typical	Maximum	Typical	Maximum	Typical	Maximum
HRU-402, 3-doubler, line-powered	N/A (OFF)	22.9	25.2	8.1	8.9	539	593
HRU-402, 4-doubler, local power	N/A (OFF)	23.7	26.1	8.0	8.8	557	613

Appendix A - Specifications 150-319-155-04, Revision 04

MAXIMUM POWER DISSIPATION

The Maximum Power Dissipation measures the power that is converted into heat that builds up within the unit. It contributes to the total heat generated in the space around the unit. It is used to determine the maximum number of fully loaded shelves per bay that does not exceed the maximum allowable power dissipation density in watts per square foot to comply with GR-63.

In COs, the maximum power dissipation for open-faced, natural convection-cooled mountings is limited to 134.7 watts per square foot per GR-63-CORE. The footprint of a standard 28-slot, 23-inch HMS-317 shelf is 7.024 square feet. Therefore, the maximum bay dissipation is limited to 946 watts. Use this limit and the parameters in Table 17 through Table 24 to determine the maximum number of HLU circuits that can occupy one CO bay.



This is a worst case situation since it assumes the entire CO is subjected to the maximum power density. More favorable conditions would permit increasing the number of shelves per bay without jeopardizing the CO thermal integrity.

The thermal loading limitations imposed when using the HLU in a Controlled Environmental Vault (CEV) or other enclosures are determined by applying its power parameters to the manufacturer's requirements for each specific housing.

The 42.5 Vdc Power Consumption is the maximum total power that the HLU-319 consumes or draws from the shelf power source. This parameter is needed when the HLU-319 is in a location remote to the CO it is serving. It determines the battery capacity required to maintain an 8-hour, stand-by battery reserve for emergency situations. Battery capacity, therefore, limits the maximum number of line units which can be installed in a remote enclosure. Use the data in Table 17 through Table 24 to perform this analysis on a case by case basis.

MAXIMUM CURRENT DRAIN

The Maximum Current Drain is the maximum current drawn from the shelf power supply when its at its minimum voltage (-42.5 Vdc). This determines the shelf fusing requirements. Use the 42.5 Vdc current data in Table 17 on page 55 through Table 24 on page 57 to determine the shelf fusing requirements for your particular HLU applications.

150-319-155-04, Revision 04 Appendix A - Specifications

HLU-319 LIST 5E CARD CONNECTOR

Figure 29 shows the card-edge connector on the HLU-319 List 5E. Active pins are highlighted in black.




Figure 29. HLU-319 List 5E Card-edge Connector

Network Management Control Bus

The HLU-319 List 5E provides a Network Management Control Bus on pin 7 of the card-edge connector. This allows the various PairGain Management System protocols to manage the HLU through the HMU-319 HiGain Management Unit. When the HLU-319 is under management, the MNGD message displays periodically on the HLU-319 List 5E front-panel display.



Some HLU-319 List 5E features are affected when it is under management. Consult the management unit practice for further information.

Appendix A - Specifications 150-319-155-04, Revision 04

Fuse Alarm

Pin 10 on the card-edge connector is a Fuse Alarm that is driven to -48 V when its onboard fuse opens. It emulates the function of the Fuse Alarm output from pin 10 on normal, high-density (HD) repeaters. Pin 10 is connected to pin 5 of the 1184 Alarm Card (slot 1 in the HD shelf) and causes the 1184 Fuse ALM LED to light when the pin 10 signal is activated. The normally floating Pin 10 output must never be driven above ground or below -80 V. It can sink a current of 10 mA. The HLU-319 does not support the BPV function (Pin E) of normal HD repeaters.

System Alarm Relay Output

Pin H on the card-edge connector (see Figure 29) is the HLU-319 List 5E System Alarm output pin. The following notes apply to Pin H:

- Pin H replaces the Local Loss of Signal (LLOS) on normal high-density (STS) repeaters.
- The normally floating output of Pin H can connect to pin 1 of the 1184 or 3192-9F Alarm Card in position 29 of the High Density (HD) shelf.
- The HLU-319 List 5E forces pin H to +5 V (maximum of 10 mA) for a system alarm condition. Pin H then remains at +5 V for the duration of the alarm condition.
- If the Wescom 1184 Alarm Card is installed in the shelf, its LOS LED lights for every MNRALM.
- The HLU-319 List 5E Status LED flashes red for the duration of a system alarm condition.
- Setting the ALM option to DIS only prevents the system alarm bus on Pin H from being activated for a system alarm event. The STATUS LED still flashes red and the ALRM message still displays.



Pin H must never be taken above +5 V or below -60 V.

150-319-155-04, Revision 04 Appendix A - Specifications

CRAFT PORT

Figure 30 shows the pinout for the craft port connector and its connection to a DB-9 or DB-25 connector on a maintenance terminal.




Figure 30. RS-232 Craft Port Pinouts

APPENDIX B - FUNCTIONAL OPERATION

PairGain HDSL technology provides full-duplex services at standard T1 rates over copper wires between an HLU and an HRU, which comprise one HiGain system. HiGain systems use PairGain 2B1Q HDSL transceiver systems to establish two, full-duplex, 784 kbps data channels between the HLU-319 and a remotely located HDU or HRU. This provides a total capacity of 1.568 Mbps between the two units.

A block diagram of the HLU-319 is shown in Figure 31. The HLU-319 receives a 1.544 Mbps DSX-1 data stream from the DSX-1 digital cross connect interface. The HLU-319 contains a DS1 frame synchronizer controlled by an 8-bit microprocessor that determines the type of framing on the DS1 stream and synchronizes to it. The HLU-319 recognizes Superframe (SF), including D4, or Extended Superframe (ESF) framing. When the data is unframed, the HLU-319 arbitrarily defines a frame bit.




Figure 31. HLU-319 List 5E Block Diagram

TIMING

The low loop wander (0.3 UI max) of an HLU-319 List 5E, when used with compatible doublers (HDU-409, HDU-404 or HDU-407) and remote units (HRU-402 or HRU-411), allows the circuit to be used in all critical timing applications, including those that are used to transport Stratum 1 timing.

GROUND FAULT DETECT

The HLU-319 List 5E has a Ground Fault Detect (GFD) circuit which detects a ground or a resistive path to ground on any wire of any loop of any span with a non-zero voltage. The circuit is not activated during low voltage mode (0 Vdc and -140 Vdc). The circuit is only active during high (±112 Vdc) voltage applications.

When the circuit is active, the system is compliant with Class A2 requirements of GR-1089. When the circuit is not active, the system is compliant with Class A3 requirements of GR-1089.

When the GFD circuit detects a grounded loop, the line power is immediately removed from the spans and a PWR FEED GND alarm is generated and displayed. The power is reapplied 30 seconds later as part of a new start-up procedure. If the ground condition persists on the span, the power is removed again once the GFD circuit detects the grounded loop.

The indication of the location of the ground fault can be obtained by monitoring the voltages on the spans on the HLU side as it sequentially powers devices in subsequent spans.

Appendix C - Compatibility 150-319-155-04, Revision 04

APPENDIX C - COMPATIBILITY

The HiGain system uses HDSL transmission technology as recommended by Bellcore TA-TSY-001210. The HiGain system complies with GR-63-CORE, TR-TSY-000499, and GR-1089-CORE.

T1 REPEATER SHELVES AND RELATED EQUIPMENT

The HLU-319 List 5E is designed to mount in the following shelves with 3192 mechanics:

- PairGain HMS-317 (28-slot, 23-inch shelf)
- PairGain HMS-318 (22-slot, 19-inch shelf)
- PairGain HMS-319 (3-slot, 19-inch horizontal shelf)
- PairGain HMS-308 (8-slot remote enclosure)
- Charles Ind. #3192 (28-slot connectorized)
- Charles Ind. #3192-9F Alarm Card
- Charles Ind. #3192-WR (28-slot wire wrap)
- Charles Ind. #343-00 (12- to 14-slot wire wrap)
- Charles Ind. #319-02 (22-slot connectorized)
- Charles Ind. #319-04 (22-slot wire wrap)
- Charles Ind. #340-00 (9- to 11-slot wire wrap)



The Charles Ind. 343-00 and 340-00 shelves do not support the HLU-319 List 5E System Alarm output on pin H. Also, if Slots 1 and 2 of these shelves were wired for the 3408 Fault Locate unit, they must be rewired to accept the HLU-319.

- Larus #1185 (28-slot connectorized)
- Larus #1184 Alarm Card

HIGAIN DOUBLER CIRCUIT DEPLOYMENT

All generations of HiGain HLU and HRU modules are compatible with each other. Although all HiGain doublers are backward-compatible with all prior HLU and HRU models, some of the circuit application enhancements of newer doubler models require that all circuit modules be of the same vintage in order to realize these enhancements. Enhanced doubler applications preclude the mixing of newer doubler models with older models of the HRU and HLU.

Table 25 on page 65 provides a matrix of HiGain doubler deployment rules to achieve maximum circuit enhancement. It lists:

- Maximum number of doublers allowed for a given circuit, depending upon the doubler and line unit models
 used to implement the circuit.
- Any restrictions on the HRU models.



All spans are fully CSA-compliant unless otherwise specified. Circuits that use more than one type of doubler are governed by the most limiting doubler rules. For example, if the HDU-451 is used with the HDU-409, use the HDU-451 deployment rules.

150-319-155-04, Revision 04 Appendix C - Compatibility

Table 25. HiGain Doubler Deployment Matrix

Maximum Number of Doublers Per Circuit (a) HDU-451, List 3, 3B, 4, 4B HDU-437, 439 HDU-404, 407, 409 Line Powered Local Powered Line Powered Local Powered Line Powered Local Powered I-CPE /-CPE /-CPE *I*-CPE *I*-CPE *I*-CPE /-CPE *I*-CPE /-CPE *I*-CPE /-CPE I-CPE **HLU Model** ON OFF ON OFF ON OFF ON OFF ON OFF ON OFF HLU-231 1 2 2 1 1 2 2 1 2 2 List 3D/6D HLU-319 List 2X; HLU-388 List 2X 2 (b) HLU-231, 2 2 1 2 2 1 2 2 2 1 1 List 7X; HLU-431, List 1D 4 (d) HLU-231. 2 (c) 3 (c) 1 2 2 1 2 2 2 2 2 Lists 8X HLU-319. Lists 5X HLU-388 Lists 5X HLU-431 List 1F 0 0 1 0 0 1 1 1 2

⁽a) HRU-411 applications with *I*-CPE "on" are limited to single doubler circuits (HDU-404, HDU-407 or HDU-409) using HLU-231, Lists 8/8A/8D/8E; HLU-319, Lists 5/5A/5D/5E; and HLU-388 Lists 5/5A/5D/5E. The HRU-412, HDU-451, HDU-437 and HDU-439 are limited to applications with one and two doublers only.

⁽b) 2000 Ω maximum loop resistance. Requires HRU-412, List 7A, List 8A or HRU-402 or HRU-411.

⁽c) Requires HRU-402 or 411.

⁽d) Requires a locally powered HRU-402.

APPENDIX D - PRODUCT SUPPORT

PairGain Customer Service Group provides expert pre-sales and post-sales support and training for all its products.

TECHNICAL SUPPORT

Technical assistance is available 24 hours a day, 7 days a week by contacting PairGain Customer Service Group at:

Telephone: 800.638.0031 or 714.832.9922

The 800 telephone support line is toll-free in the

U.S. and Canada.

Fax: 714.832.9924

Email support@pairgain.com

During normal business hours (7:30 AM to 5:30 PM, Pacific Time, Monday through Friday, excluding holidays), technical assistance calls are normally answered directly by a Customer Service Engineer. At other times, a request for technical assistance is handled by an on-duty Customer Service Engineer through a callback process. This process normally results in a callback within 30 minutes of initiating the request.

WORLD WIDE WEB

PairGain product and company information can be found at http://www.pairgain.com using any Web browser. To download PairGain product manuals from the Customer Site portion of the PairGain Web page, you need to provide a customer password. If you do not have a password, contact your PairGain sales representative.

RETURNS

To return equipment to PairGain:

- 1 Locate the number of the purchase order under which the equipment was purchased. You will need to provide this number to PairGain's Sales Administration, RMA Department, to obtain a return authorization.
- 2 Call or write PairGain's Sales Administration, RMA Department, to ask for a Return Material Authorization (RMA) number and any additional instructions. Use the telephone number, fax number or email address, listed below:

• Telephone: 800.370.9670

• Fax: 714.832.9923

• Email Address: rma@pairgain.com

- 3 Include the following information, in writing, along with the equipment you are returning:
 - Company name, address, the name of a person PairGain can contact regarding this equipment, and a phone number.
 - The purchase order number provided to the RMA Department when the RMA number was requested.

- A description of the equipment, as well as the number of units that you are returning. Be sure to include the model and part number of each unit.
- The shipping address to which PairGain should return the repaired equipment.
- The reason for the return:
 - The equipment needs an ECO/ECN upgrade.
 - The equipment is defective.



If the equipment is defective, please tell us what you observed just before the equipment malfunctioned. Be as detailed in your description as possible.

- If there is another reason for returning the equipment, please let us know so we can determine how best to help you.
- 4 Pack the equipment in a shipping carton.
- Write PairGain's address and the Return Material Authorization (RMA) Number you received from the RMA Department clearly on the outside of the carton and return to:

PairGain Technologies, Inc. 14352 Franklin Ave. Tustin, CA 92780-7013

Attention: CRF RMA (Number)



All shipments are to be returned prepaid. PairGain will not accept any collect shipments.

Appendix E - Glossary 150-319-155-04, Revision 04

APPENDIX E - GLOSSARY

2 Binary,1 Quaternary	ENFT	Enable Fractional T1
Alarm Cut Off	ES	Errored Seconds
Alarm Indication Signal indicated by transmission of an all ones pattern	ESF	Extended SuperFrame
Alarm Pattern	ESF DL	Extended SuperFrame Data Link
Alternate Mark Inversion	HCDS	High Capacity Digital Service
American Wire Gauge	HDSL	High-bit-rate Digital Subscriber Line
Bipolar with 8-zero Substitution	HDU	HiGain Doubler Unit
Bit Error Rate	HLU	HiGain Line Unit
Bipolar Violation	нмѕ	HiGain Management Shelf
Bipolar Violation Transparency	нми	HiGain Management Unit
Bridge	HRE	HiGain Remote Enclosure
Customer Disconnect Indicator	HRU	HiGain Remote Unit
Customer Installation	I-CPE	Current (amperes) requirements for Customer Premises Equipment
Common Language Equipment Identifier	ILR	Intelligent Line Repeater
Customer Local Loopback	IOR	Intelligent Office Repeater
Central Office	IR	Intelligent Repeater
Customer Premises Equipment	LED	Light Emitting Diode
Cyclic Redundancy Check	LOS	Loss of Signal
Customer Remote Loopback	LOSW	Loss of Sync Word
Carrier Service Area	NEC	National Electric Code
Channel Service Unit	NI	Network Interface
Digital Data Service	NID	Network Interface Device
Disabled	NLOC	Network Local Loopback
Digital Loop Carrier	NMA	Network Management and Administration
Digital Signal, level 0	NREM	Network Remote Loopback
Digital Signal, level 1	NVRAM	Non-volatile Random Access Memory
DS1 Cross-connect Frame	PCS	Personal Communications System
Equipment Catalog Item	PL	Payload
Enabled	POTS	Plain Old Telephone Service
	Alarm Cut Off Alarm Indication Signal indicated by transmission of an all ones pattern Alarm Pattern Alternate Mark Inversion American Wire Gauge Bipolar with 8-zero Substitution Bit Error Rate Bipolar Violation Bipolar Violation Transparency Bridge Customer Disconnect Indicator Customer Installation Common Language Equipment Identifier Customer Local Loopback Central Office Customer Premises Equipment Cyclic Redundancy Check Customer Remote Loopback Carrier Service Area Channel Service Unit Digital Data Service Disabled Digital Loop Carrier Digital Signal, level 0 Digital Signal, level 1 DS1 Cross-connect Frame Equipment Catalog Item	Alarm Cut Off Alarm Indication Signal indicated by transmission of an all ones pattern Alarm Pattern Alarm Pattern Alternate Mark Inversion Alternate Mark Inversion American Wire Gauge HDSL Bipolar with 8-zero Substitution Bit Error Rate HLU Bipolar Violation HMS Bipolar Violation Transparency HMU Bridge Customer Disconnect Indicator HRU Customer Installation I-CPE Common Language Equipment Identifier Customer Local Loopback IOR Central Office IR Customer Premises Equipment LED Cyclic Redundancy Check LOS Customer Remote Loopback Customer Remote Loopback Customer Service Area NEC Channel Service Unit Digital Data Service NID Disabled NLOC Digital Loop Carrier NMA Digital Signal, level 0 NREM Digital Signal, level 1 NVRAM DS1 Cross-connect Frame PCS Equipment Catalog Item

150-319-155-04, Revision 04 Appendix E - Glossary

PWRF	Power Feed	SPLB	Special Loopback
RCV	Receive	STS	Span Terminating Shelf
RDA	Remote DS1 Alarm	TEC	Total Error Count
RLOS	Remote Loss of Signal	TLOS	Transmit Loss of Signal-Loopback
RMA	Return Material Authorization	TSEC	Total System Error Count
SAIS	SmartJack AIS	UAS	Unavailable Seconds
SF	Super Frame	XMT	Transmit
SMJK	SmartJack		

CERTIFICATION AND WARRANTY

FCC COMPLIANCE

This unit complies with the limits for Class A digital devices pursuant to Part 15 of the FCC rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, can cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference, in which case the user will be required to correct the interference at his own expense.

Refer to the installation section of this manual for guidance on:

- Cabling
- Correct connections
- Grounding

LIMITED WARRANTY

PairGain Technologies warrants this product to be free of defects and to be fully functional for a period of 60 months of the date of original shipment, given correct customer installation and regular maintenance. PairGain will repair or replace at Pairgain's option any unit without cost during this period if the unit is found to be defective for any reason other than abuse or incorrect use or installation.

Do not try to repair the unit. If it fails, replace it with another unit and return the faulty unit to PairGain for repair. Any modifications of the unit by anyone other than an authorized PairGain representative voids the warranty.

If a unit needs repair, call PairGain for a Return Material Authorization (RMA) number and return the defective unit, freight prepaid, along with a brief description of the problem, to:

PairGain Technologies, Inc. 14352 Franklin Avenue Tustin, CA 92780 ATTN: Repair and Return Dept. 800.638.0031

PairGain continues to repair faulty modules beyond the warranty program at a nominal charge. Contact your PairGain sales representative for details and pricing.

MODIFICATIONS

Any changes or modifications made to this device that are not expressly approved by PairGain Technologies, Inc. may void the user's warranty. All wiring external to the products should follow the provisions of the current edition of the National Electrical Code.

STANDARDS COMPLIANCE

The HLU-319 List 5E has been tested and verified to comply with the applicable sections of the following standards.

- GR 63-CORE Network Equipment-Building System (NEBS) Requirements
- GR 1089-CORE Electromagnetic Compatibility and Electrical Safety

UL LISTING AND CUL MARK

The HLU-319 List 5E Line Unit is listed with Underwriters Laboratories and meets all applicable Canadian safety standards of the CUL Mark.

Use caution when installing or modifying telephone lines. Dangerous voltages may be present. Do not install telephone wiring during a lightning storm. Always disconnect telephone lines and power connections from wall outlets before servicing or disassembling this equipment.

All wiring external to the product should follow the provisions of the current edition of the National Electrical Code.

Corporate Office

14402 Franklin Avenue Tustin, CA 92780

Tel: 714.832.9922 Fax: 714.832.9924

For Technical Assistance:

800.638.0031

